

AD A091088

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
National Dam Safety AD A091088		Number NY 725
4. TITLE (and Subtitle) Phase I Inspection Program Millbrook Watershed Project Site (Inventory) Susquehanna River Basin, Chenango County, NY Inventory, Nov 25 New York - Phase I		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) George Koch		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 30 September 1980
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		13. NUMBER OF PAGES
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES THIS DOCUMENT IS BEST QUALITY PRACTICABLE. THE COPY FURNISHED TO DDC CONTAINS A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability		Original contains color plates: All DTIC reproduct- ions will be in black and white
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.  The examination of documents and a visual inspection of the Mill Brook Site 1 Dam did not reveal conditions which constitute a hazard to human life or property.		NOV 3 1980

> The total discharge capacity of the spillways is adequate to impound and safely discharge the floodwaters resulting from the Probable Maximum Flood (PMF). ~~✓~~

Several minor deficiencies were noted which should be corrected within 6 months of the date of final approval of this report. The required actions are establishing a good grass cover on the upstream slope, repairing the sloughing on the outer auxiliary spillway slope, and regrading the eroded area at the end of the rock sill on the downstream end of the auxiliary spillway channel. In addition, an emergency action plan for notification of downstream residents should be developed within the same time frame.

**SUSQUEHANNA RIVER BASIN**  
**MILLBROOK WATERSHED PROJECT**  
**SITE I**

CHENANGO COUNTY, NEW YORK  
INVENTORY NO. N.Y. 715

**PHASE I INSPECTION REPORT**  
**NATIONAL DAM SAFETY PROGRAM**



D  
U

*DACW-51-79-C-0001*

NEW YORK DISTRICT CORPS OF ENGINEERS

AUGUST, 1980

APPROVED FOR PUBLIC RELEASE  
DISTRIBUTION STATEMENT  
CONTRACT NO. DACW-51-79-C0001

80 10 29 007

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS	GRA&I
DTIC	TAB
Unannounced	
Justification	
By	
Distrib	
Availability Codes	
Avail and/or	
Dist	Special
29 041	

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
MILL BROOK WATERSHED PROJECT SITE I I.D. No. NY-715  
(#117B-4340 SUSQUEHANNA RIVER BASIN)  
CHENANGO COUNTY

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 GEOTECHNICAL DATA	4
2.2 DESIGN RECORDS	4
2.3 CONSTRUCTION RECORDS	4
2.4 OPERATION RECORDS	5
2.5 EVALUATION OF DATA	5
3 VISUAL INSPECTION	6
3.1 FINDINGS	6
3.2 EVALUATION OF OBSERVATIONS	7
4 OPERATION AND MAINTENANCE PROCEDURES	8
4.1 PROCEDURES	8
4.2 MAINTENANCE OF DAM	8
4.3 WARNING SYSTEM IN EFFECT	8
4.4 EVALUATION	8

	<u>PAGE NO.</u>
5 HYDROLOGIC/HYDRAULIC	9
5.1 DRAINAGE AREA CHARACTERISTICS	9
5.2 ANALYSIS CRITERIA	9
5.3 SPILLWAY CAPACITY	9
5.4 RESERVOIR CAPACITY	9
5.5 FLOODS OF RECORD	9
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	9
6 STRUCTURAL STABILITY	10
6.1 EVALUATION OF STRUCTURAL STABILITY	10
7 ASSESSMENT/RECOMMENDATIONS	11
7.1 ASSESSMENT	11
7.2 RECOMMENDED MEASURES	11

#### APPENDIX

- A. PHOTOS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC: ENGINEERING DATA AND COMPUTATIONS
- D. STABILITY COMPUTATIONS
- E. REFERENCES
- F. DRAWINGS

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Mill Brook Watershed Project Site 1  
I.D. No. NY-715

State Located: New York

County Located: Chenango

Watershed: Susquehanna River Basin


Date of Inspection: July 31, 1980

ASSESSMENT

The examination of documents and a visual inspection of the Mill Brook Site 1 Dam did not reveal conditions which constitute a hazard to human life or property.


The total discharge capacity of the spillways is adequate to impound and safely discharge the floodwaters resulting from the Probable Maximum Flood (PMF).

Several minor deficiencies were noted which should be corrected within 6 months of the date of final approval of this report. The required actions are establishing a good grass cover on the upstream slope, repairing the sloughing on the outer auxiliary spillway slope, and regrading the eroded area at the end of the rock sill on the downstream end of the auxiliary spillway channel. In addition, an emergency action plan for notification of downstream residents should be developed within the same time frame.




George Koch  
Chief, Dam Safety Section  
New York State Department  
of Environmental Conservation  
NY License No. 45937

Approved By:

  
Colonel W. M. Smith Jr.  
New York District Engineer

Date:







OVERVIEW  
MILL BROOK WATERSHED PROJECT  
SITE 1  
I.D. No. NY-715

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
MILL BROOK WATERSHED PROJECT  
SITE 1  
I.D. No. NY-715  
(#117B-4340)  
SUSQUEHANNA RIVER BASIN  
CHENANGO COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam

The Mill Brook Watershed Project Site 1 Dam consists of an earth dam with a service spillway pipe passing through the embankment and an excavated auxiliary spillway passing around the southern end of the dam.

The dam consists of a compacted earth embankment which is 52 feet high, has a crest length of 475 feet and a crest width of 14 feet. The upstream slope is 1 vertical on 3.5 horizontal with a 10 foot wide berm near the base of the slope. The downstream slope is 1 vertical on 2.5 horizontal with a 12 foot wide berm at approximately the mid-point of the slope. Below the berm, the slope flattens to a 1 on 3 (V:H). The crest and exposed slopes are covered with grass. An earth cutoff trench of varying depth and width keys the embankment into the foundation soils.

The service spillway consists of a rectangular reinforced concrete drop inlet structure, a 30 inch diameter reinforced concrete pipe with anti-seepage collars and a riprapped plunge pool. A reservoir drain consisting of an 18 inch diameter concrete pipe extends from the upstream toe of the embankment to the base of the spillway riser. A vertical slide gate mechanism mounted along the inside of the riser controls the flow through the reservoir drain. The auxiliary spillway is an earth cut with a bottom width of 100 feet.

An internal drainage system consisting of a gravel and stone filter is located at the base of the embankment near the downstream toe. Seepage is conducted through this drain to beyond the toe of the embankment via twin 6 inch diameter asbestos-cement pipes.

b. Location

The Mill Brook Watershed Project Site 1 dam is located off the Sherburne Turnpike in the Town of New Berlin. The structure is approximately 1 mile north-west of the Village of New Berlin.

c. Size Classification

The dam is 52 feet high and has a maximum storage capacity of almost 400 acre-feet. Therefore, the dam is in the intermediate size category as defined by the "Recommended Guidelines for Safety Inspection of Dams."

d. Hazard Classification

This dam is classified as "high" hazard due to the presence of a number of homes in the Village of New Berlin located downstream of the dam.

e. Ownership

The dam is owned by Chenango County, New York. The contracting officer is Mr. Phillip Cummings whose telephone number is (607)334-4632.

f. Purpose of Dam

The dam is a floodwater retarding structure.

g. Design and Construction History

The dam was designed by the U.S. Department of Agriculture, Soil Conservation Service (SCS). The SCS office at the Broome County Airport has a design folder containing hydrologic, hydraulic and structural design information. The dam was constructed between 1977 and 1979 by J.R. Hall, Inc. of Waterville, New York. The Howdy Jones Construction Company was the earthwork subcontractor for the structure.

h. Normal Operating Procedures

Normal flows are discharged through the service spillway. This structure has sufficient capacity to store and discharge a 100 year flood without discharge occurring in the auxiliary spillway. For storms in excess of the 100 year flood, discharge through the auxiliary spillway can be expected.

1.3 PERTINENT DATA

<u>a. Drainage Area (acres)</u>	1338
<u>b. Discharge at Dam (cfs)</u>	
Service Spillway at maximum high water	158
Service Spillway at auxiliary spillway crest elev.	144
Auxiliary Spillway at maximum high water	8850
Reservoir drain at service spillway crest elevation	79

c. Elevation(USGS Datum)

Top of Dam	1349.0
Auxiliary Spillway Crest	1339.5
Service Spillway Crest	1306.3
Reservoir Drain (invert elevation)	1302.0

d. Reservoir Surface Area (acres)

Top of Dam	22.7
Auxiliary Spillway Crest	15.0
Service Spillway Crest	0.9

e. Storage Capacity (acre-feet)

Top of Dam	397.9
Auxiliary Spillway Crest	222.6
Service Spillway Crest	2.2

f. Dam

Embankment type - A compacted earth fill with a keyed earth cut-off trench, and a drain parallel to the axis of dam

Embankment length (ft) 475

Slopes - Upstream 1 vertical on 3.5 horizontal  
Downstream 1 vertical on 2.5 horizontal  
with 12 foot wide berm - slope below  
berm is 1 vertical on 3 horizontal

Crest Width (ft) 14

g. Service Spillway

Type: Ungated, reinforced concrete drop inlet (2.5 x 7.5 ft), rising 8.3 feet above the invert of the 30 inch diameter concrete conduit; length of conduit 340 feet

Weir length (ft). 15

h. Auxiliary Spillway

Type: An excavated, trapezoidal channel with a grass lining.

Bottom Width (ft) 100

Side Slopes (V:H) 1:3

Exit Slope (ft/ft) 0.02

i. Reservoir Drain

Type: 18 inch diameter reinforced concrete pipe

Control: Manually operated vertical slide gate mounted along the inside of the service spillway riser.

## SECTION 2: ENGINEERING DATA

### 2.1 GEOTECHNICAL DATA

#### a. Geology

The Mill Brook Watershed Project Site 1 Dam is located in the glaciated portion of the Appalachian uplands (northern extreme of the Appalachian Plateau) physiographic province of New York State. These uplands were formed by dissection of the uplifted but flat lying sandstones and shales of the Middle and Upper Catskill Delta. The plateau surface is represented by flat-topped divides with drainage generally southwest toward the Susquehanna River system. The bedrock in the vicinity of this dam is predominantly shale.

The present surficial deposits consist of a thin layer of topsoil over glacial till. There is a small amount of outwash and alluvial gravel in the vicinity of the present stream channel. These deposits have resulted from glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation.

#### b. Subsurface Investigations

A subsurface investigation program was conducted by SCS. The initial test pits and drill holes were progressed in 1969 and a supplemental program was undertaken in 1977. A total of 17 borings and 14 test pits were taken at locations along the dam, auxiliary spillway, structural elements and borrow area. Applicable subsurface information has been included in Appendix F.

The centerline of the structure was shifted a short distance downstream from the originally proposed location because of foundation conditions encountered during the drilling program. In general, the foundation consists of glacial till over bedrock. The depth to bedrock in the vicinity of the dam varies from 5 to 50 feet. The soils encountered varied from slightly to moderately permeable.

### 2.2 DESIGN RECORDS

This dam was designed by the Soil Conservation Service, who prepared a design report. A folder containing the design report and other design information was available at the SCS office at the Broome County Airport. Twenty four drawings, several of which have been included in Appendix F, were prepared for the construction of this dam.

### 2.3 CONSTRUCTION RECORDS

Complete construction records are available from the SCS office at the Broome County Airport. Several changes from the original design were made during construction. These changes have been indicated on the as-built plans shown in Appendix F. Among the changes were the flattening of the southern cut slope which forms the auxiliary spillway and the addition of rock creases at the embankment-abutment interface.

#### 2.4 OPERATION RECORDS

Since the dam is an uncontrolled, floodwater retarding structure, no operating records are maintained regarding water levels. However, during periods of heavy rainfall, SCS personnel do monitor reservoir levels.

#### 2.5 EVALUATION OF DATA

The data presented in this report has been compiled from information obtained from the Soil Conservation Service as well as the New York State Department of Environmental Conservation files. It appears to be adequate and reliable for Phase I inspection purposes.

### SECTION 3: VISUAL INSPECTION

#### 3.1 FINDINGS

##### a. General

Visual inspection of the Site 1 dam was conducted on July 31, 1980. The weather was clear and the temperature was in the seventies. The water surface at the time of the inspection was 3.74 feet below the top of the concrete riser.

##### b. Embankment

No signs of distress were observed in the earth embankment and no evidence of seepage, misalignment, subsidence or surface cracking were noted on the embankment. The only deficiencies noted were of a minor nature and most were related to the fact that construction of the dam was completed only last September. The grass cover on the upstream slope had not yet established itself. There was minor rill erosion between the top of the riser and the northern abutment contact. There was also some minor erosion on the lower portion of the downstream slope between the principal spillway outlet pipe and the northern abutment.

An internal drainage system composed of 2 - 6 inch diameter pipes surrounded by drain-fill material provides drainage at the base of the embankment. At the time of the inspection, there was no flow coming from the pipes. However, Gary Page of SCS reported that the drains had operated during the construction of the dam.

##### c. Service Spillway

The service spillway consists of a vertical drop inlet structure, a reinforced concrete pipe and a plunge pool at the conduit outlet. The elements which were visible appeared to be in good condition. The pipe interior had been closely inspected in June of 1980 by Mr. Page. His inspection indicated that the maximum joint extensibility along the conduit was three-quarters of an inch. This compares favorably with the maximum closure achieved during construction of one-half inch.

##### d. Auxiliary Spillway

The auxiliary spillway is located in an earth cut at the southern end of the dam. The cut slope on the outside of the channel was sloughing in several areas. This sloughing was caused by water coming out of the hillside. The downstream portion of this slope had been flattened during construction in an attempt to remedy these problems. However, even in the flattened area there were several locations where sloughing was observed. In addition, there was some erosion at the end of the rock sill which extends across the downstream end of the auxiliary spillway channel.

##### e. Reservoir Drain

The 18 inch diameter reservoir drain and manually operated slide gate may be used to lower the reservoir. The drain was reported to be operational.

##### f. Reservoir

There were no signs of serious soil instability in the reservoir area. However, there was a minor sedimentation delta in the reservoir from an old haul road which extends into the pool.

g. Downstream Channel

The downstream channel below the plunge pool was gravel and stone filled for a distance. Beyond the area which was disturbed by construction, the channel was cut into natural ground. Trees and heavy brush were growing at the edge of the channel.

3.2 EVALUATION OF OBSERVATIONS

Visual inspection of this dam revealed the following deficiencies:

1. The grass cover on the upstream slope was relatively sparse.
2. There was substantial sloughing on the outside cut slope of the auxiliary spillway channel.
3. There was some erosion at the end of the rock sill at the downstream end of the auxiliary spillway channel.



#### SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

##### 4.1 PROCEDURES

The normal water surface elevation is at the crest of the principal spillway riser. Downstream flows are limited by flow into the riser, except during periods of extremely heavy runoff when the auxiliary spillway is in service.

##### 4.2 MAINTENANCE OF DAM

The dam is maintained by the owner. Construction of the dam was completed in September 1979. The grass on the upstream slope has not come in uniformly and might need further attention. In other respects, the dam appeared to be satisfactorily maintained.

##### 4.3 WARNING SYSTEM IN EFFECT

There is no warning system in effect.

##### 4.4 EVALUATION

The operation and maintenance procedures for this dam are satisfactory.

## SECTION 5: HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the 1338 acre watershed of the Site 1 dam was made using the USGS 7.5 minute quadrangles for New Berlin North and Sherburne, New York. The watershed consists of open grassed fields and woodlands. Relief in the drainage area ranges from moderate to steep.

### 5.2 ANALYSIS CRITERIA

The analysis of the floodwater retarding capability of this dam was performed using the Corps of Engineers HEC-1 computer program, Dam Safety version. This program develops an inflow hydrograph using the Snyder Synthetic Unit Hydrograph method and then uses the "Modified Puls" flood routing procedure. The spillway design flood selected was the Probable Maximum Flood (PMF) in accordance with the Recommended Guidelines of the U.S. Army Corps of Engineers.

### 5.3 SPILLWAY CAPACITY

The principal and auxiliary spillways are uncontrolled structures. The capacities for both spillways were taken from the stage-discharge data included in the SCS design report.

The spillways have sufficient capacity for discharging the peak outflow from the PMF. For this storm, the peak inflow is 3584 cfs and the peak outflow is 3542 cfs. When the spillways are discharging the peak outflow, the water surface will be 4.5 feet below the top of the dam. Further information concerning this analysis is included in Appendix C.

### 5.4 RESERVOIR CAPACITY

Normal flood control storage capacity of the reservoir between the principal and auxiliary spillways is 220.4 acre-feet which is equivalent to a runoff depth of 2.0 inches over the drainage area. Surge storage capacity to the maximum high water elevation is an additional 175.3 acre-feet, equivalent to a runoff depth over the drainage area of 1.6 inches. Total storage capacity of the dam is 397.9 acre-feet.

### 5.5 FLOODS OF RECORD

The maximum known flood occurred during March, 1978 while the dam was under construction. The pool level at this time was reported to be about elevation 1323.5. No higher water has been recorded since the dam was completed in September, 1979.

### 5.6 OVERTOPPING POTENTIAL

Analysis indicates that the total discharge capacity is sufficient to prevent overtopping from the PMF.

### 5.7 EVALUATION

This dam has sufficient capability to impound and adequately discharge floodwaters expected to result from the PMF.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

No signs of distress were observed in connection with the earth embankment.

#### b. Design and Construction Data

Design data was obtained from SCS. Stability analyses were performed using the Swedish circle method of analysis. Two undrained triaxial shear tests were performed on compacted soil samples from the proposed borrow area. These tests were used to select soil parameters for use in the analysis. Several cases were analyzed on the upstream slope. For rapid drawdown from the permanent pool elevation, the minimum factor of safety was 1.45. For rapid-draw down from the water surface which would result from the 100 year storm, the factor of safety was 1.2. While this is lower than desirable, it is acceptable due to the low frequency of occurrence of this storm. For the downstream slope, long term steady seepage was analyzed. The minimum factor of safety for this case was 1.34.

#### c. Seismic Stability

No records of any seismic stability analysis performed for this structure could be located.

## SECTION 7: ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

The Phase I inspection of the Mill Brook Site 1 Dam did not reveal conditions which constitute a hazard to human life or property. The earth embankment is considered to be stable and the spillways are capable of retarding and safely discharging floodwaters resulting from the Probable Maximum Flood (PMF).

#### b. Adequacy of Information

Information reviewed for Phase I inspection purposes is considered to be adequate.

#### c. Need for Additional Investigations

No additional investigations are necessary at this time.


### 7.2 RECOMMENDED MEASURES

The following actions should be taken within 6 months of the date of final approval of this report:

- a. Take actions which will assist in the development of a good grass cover on the upstream slope.
- b. Investigate the sloughing on the outside cut slope of the auxiliary spillway channel and take actions necessary to correct this problem.
- c. Repair the erosion at the end of the rock sill at the downstream end of the auxiliary spillway channel.
- . Develop an emergency action plan for notification of downstream residents and the proper authorities in the event of large auxiliary spillway discharges.

APPENDIX A

PHOTOGRAPHS




Service Spillway Riser



Upstream Slope of Dam and Service  
Spillway Riser



Downstream Slope - Auxiliary Spillway  
Channel in Background



Outlets of Principal Spillway Conduit  
and Drainage System Pipes



Crest of Dam Looking Across  
Auxiliary Spillway Channel




Rock Trench Carrying Flow Off  
Road into Pool, Slight Delta Forming at Toe





Auxiliary Spillway Channel Looking Downstream  
Note Sloughing on Slope



Sloughing on Outer Slope of Auxiliary  
Spillway Channel

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam MILL BROOK WATERSHED PROJECT SITE 1  
Fed. I.D. # NY 715 DEC Dam No. 117B-4340  
River Basin SUSQUEHANNA  
Location: Town NEW BERLIN County CHENANGO  
Stream Name MILL BROOK  
Tributary of UNADILLA RIVER  
Latitude (N) 42° 37.9' Longitude (W) 75° 20.8'  
Type of Dam EARTH EMBANKMENT  
Hazard Category C  
Date(s) of Inspection JULY 31, 1980  
Weather Conditions SUNNY 75°  
Reservoir Level at Time of Inspection 3.74' BELOW TOP OF RISER

b. Inspection Personnel W. LYNICK R. WARRENDER

c. Persons Contacted (Including Address & Phone No.) \_\_\_\_\_

GARY PAGE - SCS BROOME CO. AIRPORT OFFICE  
607-773-2751

d. History:

Date Constructed 9/79 COMPLETED Date(s) Reconstructed \_\_\_\_\_

Designer SOIL CONSERVATION SERVICE

Constructed By J.R. HALL INC. - WATERVILLE, N.Y. SUB- HOWARD JONES CONST.  
(EARTH)

Owner CHENANGO COUNTY

2) Embankment

a. Characteristics

- (1) Embankment Material COMPACTED TILL
- (2) Cutoff Type COMPACTED EARTH
- (3) Impervious Core NONE
- (4) Internal Drainage System YES
- (5) Miscellaneous GRASS COVER - NO CROWN VETCH AVAILABLE AT TIME OF CONSTRUCTION

b. Crest

- (1) Vertical Alignment GOOD
- (2) Horizontal Alignment CURVED
- (3) Surface Cracks NONE
- (4) Miscellaneous

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1 ON 3
- (2) Undesirable Growth or Debris, Animal Burrows NONE - GRASS COVER WAS SOMEWHAT SPARSE
- (3) Sloughing, Subsidence or Depressions MINOR RILL EROSION BETWEEN TOP OF RISER & NORTH ABUTMENT CONTACT & AROUND RISER AREA ON SLOPE

(4) Slope Protection NONE

(5) Surface Cracks or Movement at Toe NONE

d. Downstream Slope

(1) Slope (Estimate - V:H) 1 ON 2 UPPER 1 ON 3 LOWER

(2) Undesirable Growth or Debris, Animal Burrows NONE

(3) Sloughing, Subsidence or Depressions MINOR EROSION RILL ON LOWER BERM SLOPE (1/2 WAY BETWEEN PIPE & NORTH ABUTMENT)

(4) Surface Cracks or Movement at Toe NONE

(5) Seepage NONE

(6) External Drainage System (Ditches, ~~Trenches~~; ~~Blanket~~) RIPRAP AT ALL 4 SLOPE-ABUTMENT CONTACTS

(7) Condition Around Outlet Structure SATISFACTORY-RIPRAP

(8) Seepage Beyond Toe NONE

e. Abutments - Embankment Contact

RIPRAP ON CREASES

(1) Erosion at Contact NONE

(2) Seepage Along Contact NONE

3) Drainage System

a. Description of System 2- 6" DIAMETER ASBESTOS-CEMENT  
PIPE WITH ANIMAL GUARDS

b. Condition of System OKAY- GARY PAGE SAID HIGH WATER DURING  
CONSTRUCTION CAUSED PIPES TO FLOW SUBSTANTIALLY

c. Discharge from Drainage System NONE

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs,  
Piezometers, Etc.)

NONE

5) Reservoir

- a. Slopes STEEP WITH BRUSH & TREES
- b. Sedimentation MINOR DELTA AT OLD HAUL ROAD & DITCH  
ENTRANCE FROM RIGHT ABUTMENT AT AUXILIARY SPILLWAY ENTRANCE
- c. Unusual Conditions Which Affect Dam NONE

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) VILLAGE OF  
NEW BERLIN
- b. Seepage, Unusual Growth NONE
- c. Evidence of Movement Beyond Toe of Dam NONE
- d. Condition of Downstream Channel HEAVY BRUSH & TREES IN  
STREAM

7) Spillway(s) (Including Discharge Conveyance Channel)

- a. General CONCRETE RISER → CONDUIT → PLUNGE POOL FOR  
SERVICE SPILLWAY  
AUXILIARY SPILLWAY - CHANNEL IN EARTH CUT
- b. Condition of Service Spillway SATISFACTORY  
GARY PAGE CRAWLED PIPE IN JUNE, 1980 - HE SAID  
MAXIMUM JOINT EXTENSIBILITY WAS  $\frac{3}{4}$ " - THE MAXIMUM  
CLOSURE AT THE TIME OF CONSTRUCTION WAS  $\frac{1}{2}$ ".  
MOST OF THE JOINTS HAD  $\leq \frac{3}{8}$ " GAP.

- c. Condition of Auxiliary Spillway SLoughing ON OUTSIDE CUT SLOPE  
(CAUSED BY HILLSIDE SEEPAGE 2 MONTHS EACH YEAR). SLOPE  
WAS FLATTENED DURING CONSTRUCTION ON PART OF CHANNEL BUT  
THERE WAS STILL MINOR SLOUGHING IN FLAT AREA  
ROCK SILL AT OUTLET TO AUXILIARY SPILLWAY WAS ERODED AT ONE END

- d. Condition of Discharge Conveyance Channel \_\_\_\_\_  
DOWNSTREAM OF SITE - HEAVY BRUSH & TREES LINING  
EXISTING STREAM

8) Reservoir Drain/Outlet

Type: Pipe ☒ Conduit \_\_\_\_\_ Other \_\_\_\_\_

Material: Concrete ☒ Metal \_\_\_\_\_ Other \_\_\_\_\_

Size: 18" Length 30'

Invert Elevations: Entrance 1302.0 Exit 1302.0

Physical Condition (Describe): \_\_\_\_\_ Unobservable ☒

Material: \_\_\_\_\_

Joints: \_\_\_\_\_ Alignment \_\_\_\_\_

Structural Integrity: \_\_\_\_\_

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate ☒ Valve \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Operation: Operable ☒ Inoperable \_\_\_\_\_ Other \_\_\_\_\_

Present Condition (Describe): \_\_\_\_\_

REPORTED TO BE OPERATIONAL



9) Structural

- a. Concrete Surfaces ALL SATISFACTORY
- b. Structural Cracking NONE
- c. Movement - Horizontal & Vertical Alignment (Settlement) NONE
- d. Junctions with Abutments or Embankments GOOD
- e. Drains - Foundation, Joint, Face
- f. Water Passages, Conduits, Sluices SLIGHT SEPARATION OF SOME JOINTS
- g. Seepage or Leakage NONE

h. Joints - Construction, etc. \_\_\_\_\_

NONE

i. Foundation OKAY

j. Abutments OKAY

k. Control Gates \_\_\_\_\_

l. Approach & Outlet Channels \_\_\_\_\_

m. Energy Dissipators (Plunge Pool, etc.) RIPRAP PLUNGE POOL

n. Intake Structures GOOD CONDITION

o. Stability \_\_\_\_\_

p. Miscellaneous \_\_\_\_\_

APPENDIX C

HYDROLOGIC/HYDRAULIC  
ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1349.0</u>	<u>22.7</u>	<u>397.9</u>
2) Design High Water (Max. Design Pool)	<u>          </u>	<u>          </u>	<u>          </u>
3) Auxiliary Spillway Crest	<u>1339.5</u>	<u>15.0</u>	<u>222.6</u>
4) Pool Level with Flashboards	<u>          </u>	<u>          </u>	<u>          </u>
5) Service Spillway Crest	<u>1306.3</u>	<u>0.9</u>	<u>2.2</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>          </u>
2) Spillway @ Maximum High Water	<u>158.4</u>
3) Spillway @ Design High Water	<u>          </u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>143.5</u>
5) Low Level Outlet	<u>79.2</u>
6) Total (of all facilities) @ Maximum High Water	<u>9009</u>
7) Maximum Known Flood	<u>          </u>
8) At Time of Inspection	<u>          </u>

CREST:

ELEVATION: 1349.0Type: GRASSED EARTHWidth: 16'Length: 475'Spillover AUXILIARY CHANNELLocation SOUTH END OF DAM

SPILLWAY:

PRINCIPAL

EMERGENCY

1306.3

Elevation

1339.5R/C DROP INLET

Type

EARTH CUT CHANNELWEIR LENGTH 15'

Width

100'

Type of Control

✓

Uncontrolled

✓

Controlled:

Type

(Flashboards; gate)

Number

Size/Length

Invert Material

Anticipated Length  
of operating service

Chute Length

Height Between Spillway Crest  
& Approach Channel Invert  
(Weir Flow)

HYDROMETEROLOGICAL GAGES:

Type : NONE

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

RESERVOIR DRAIN

DRAINAGE AREA: 2.09 SQ.M.

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: FARMS, WOODLANDS

Terrain - Relief: GRASS - FORESTS

Surface - Soil: TILL

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

NONE

Potential Sedimentation problem areas (natural or man-made; present or future)

CONSTRUCTION ROAD GOES INTO RESERVOIR

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

NONE

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: \_\_\_\_\_

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool \_\_\_\_\_ (Miles)

Length of Shoreline (@ Spillway Crest) \_\_\_\_\_ (Miles)

PROJECT GRID

JOB MILL BROOK WATERSHED PROJECT		SHEET NO. 1	CHECKED BY	DATE
SUBJECT HYDROLOGIC / HYDRAULIC COMPUTATIONS		COMPUTED BY JLG		DATE 1-25-80
DRAINAGE AREA = 2.09 SQ MI = 1338 ACRES				
SYDER SYNTHETIC UNIT HYDROGRAPH				
L = 2.46 mi      L <sub>ca</sub> = 1.21 mi				
$t_p = C(L + L_{ca})^2 = 2.0(2.46 + 1.21)^2 = 2.77$				
$t_r = \frac{t_p}{5.5} = \frac{2.77}{5.5} = .50$ USE $\frac{1}{2}$ HOUR INCREMENTS				
$t_{rr} = t_p + .25(t_p + t_r) = 2.77 + .25(2.77 + .50) = 4.71$				
HR #33 PMP RAIN = 8.22				
ZONE = 1 PMP K <sub>W</sub> = 20 IN				
CWA = 111%				
ZWR = 133%				
ZBS = 125%				
ZFT = 142%				
$TRSPC = 1 - \frac{.3009}{(2.09)^{.1477}} = .74$				
BASE FLOW = USE 2 cfs				



黃帝學心書卷之六

A1 :ILL BRCKK WATERSHED PROJECT SITE 1  
 A2 ANALYSIS PNF WITH RATIOS

AGE	DATE	TIME
8	20C	5
81		

17

5. 11

٢٠

18

一一

٢٩

↑

2.77

2X

—

TY 1137

1

•

•

- 
- 
- 
- 

4

•

6

3

2

\*\*\*\*\*  
 FLOW HYDROGRAPH PACKAGE (HFC-1)  
 (A) SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 MODIFIED FOR HYPERVFL APR 79  
 \*\*\*\*\*

\*\*\*\*\*  
 NEW YORK STATE  
 DEPT OF ENVIRONMENTAL CONSERVATION  
 FLOOD PROTECTION BUREAU  
 \*\*\*\*\*

FILE DATE 07/28/80

MILL BROOK WATERSHED PROJECT SITE 1  
 ANALYSIS PMF WITH RATIOS  
 DATE

NC NHR NPIN IDAY IHP IMIN METRC  
 20C 0 30 0 0 0 0  
 JOPER 5 JOPER 5 NWT LRPT TRACE  
 0 0 0 0 0 0

JOB SPECIFICATION

MULTI-PLAN ANALYSES TO BE PERFORMED  
 PLAN= 1 NRTO= 2 LRTIO= 1  
 RTICS= 0.50 1.00

\*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*  
 \*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

1 FLOW HYDROGRAPH

ISTAQ 1 ICOMP 0 IECON 0 ITAPE 0 JPLT 0 JPRT C INAME 1 ISTAGE 1 IAUTO 0

IHYOG 1 IUNG 1 TAREA 2.09 SNAP 0. TRSDA 2.09 TRSPC 0.74 RATIC 0. ISNEW 0 ISAME 1 LOCAL 0

PRECIP DATA  
 R6 R12 R24 R48 R72 R96  
 0. 20.00 111.00 123.00 132.00 142.00 0. 0. 0. 0. 0. 0.

LOSS DATA  
 LROPT 0 STRKR 0. DLTKR 0. RTIOL 1.00 ERAIN 0. STRKS 0. RTIOK 1.00 STRTL 1.00 CNSTL 0.10 ALSMX 0. RTIMP 0.

UNIT HYDROGRAPH DATA  
 TP= 2.77 CP=0.63 NTA= 0

REFLECTION DATA

STRTQ= 2.00 QPCSN= 2.00 RTICR= 1.00  
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 6.41 AND R= 5.12 INTERVALS

UNIT HYDROGRAPH 31 END-OF-PERIOD ORDINATES, LAG= 2.79 FCLT, CP= 0.63 VOL= 1.00  
 21. 76. 15C. 226. 282. 305. 285. 240. 197. 162.  
 133. 11C. 90. 74. 61. 50. 41. 34. 28. 23.  
 15. 13. 10. 9. 7. 6. 5. 4. 3. 3.

END-OF-PERIOD FLOW  
 HO.DA HP.MN PERIOD EXCS LOSS COMP Q HO.DA PERIOD EXCS LOSS COMP Q  
 1.01 0.30 1 0.00 0.00 2. 1.03 2.30 101 0. 0. 0. 0. 263.  
 1.01 1.00 2 0.00 0.00 2. 1.03 3.60 102 0. 0. 0. 0. 217.  
 1.01 1.30 3 0.00 0.00 2. 1.03 3.60 102 0. 0. 0. 0. 217.

145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39	38	37	36	35	34	33	32	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
145	143	142	141	140	139	138	137	136	135	134	133	132	131	130	129	128	127	126	125	124	123	122	121	120	119	118	117	116	115	114	113	112	111	110	109	108	107	106	105	104	103	102	101	100	99	98	97	96	95	94	93	92	91	90	89	88	87	86	85	84	83	82	81	80	79	78	77	76	75	74	73	72	71	70	69	68	67	66	65	64	63	62	61	60	59	58	57	56	55	54	53	52	51	50	49	48	47	46	45	44	43	42	41	40	39																																							

1.02	11.00	70	0.15	0.10	0.05	193.	1.04	14.00	170	0.	0.	0.	2.
1.02	11.30	71	0.15	0.10	0.05	206.	1.04	13.30	171	0.	0.	0.	2.
1.02	12.00	72	0.15	0.10	0.05	217.	1.04	14.00	172	0.	0.	0.	2.
1.02	12.30	73	0.82	0.77	0.05	239.	1.04	14.30	173	0.	0.	0.	2.
1.02	13.00	74	0.82	0.77	0.05	298.	1.04	15.00	174	0.	0.	0.	2.
1.02	13.30	75	0.99	0.94	0.05	409.	1.04	15.30	175	0.	0.	0.	2.
1.02	14.00	76	0.99	0.94	0.05	578.	1.04	16.00	176	0.	0.	0.	2.
1.02	14.30	77	1.23	1.18	0.05	802.	1.04	16.30	177	0.	0.	0.	2.
1.02	15.00	78	1.23	1.18	0.05	1067.	1.04	17.00	178	0.	0.	0.	2.
1.02	15.30	79	1.50	1.45	0.05	1351.	1.04	17.30	179	0.	0.	0.	2.
1.02	16.00	80	4.74	4.69	0.05	1709.	1.04	18.00	180	0.	0.	0.	2.
1.02	16.30	81	1.15	1.10	0.05	2172.	1.04	18.30	181	0.	0.	0.	2.
1.02	17.00	82	1.15	1.10	0.05	2672.	1.04	19.00	182	0.	0.	0.	2.
1.02	17.30	83	0.90	0.85	0.05	3129.	1.04	19.30	183	0.	0.	0.	2.
1.02	18.00	84	0.90	0.85	0.05	3455.	1.04	20.00	184	0.	0.	0.	2.
1.02	18.30	85	0.07	0.02	0.05	3584.	1.04	20.30	185	0.	0.	0.	2.
1.02	19.00	86	0.07	0.02	0.05	3468.	1.04	21.00	186	0.	0.	0.	2.
1.02	19.30	87	0.07	0.02	0.05	3168.	1.04	21.30	187	0.	0.	0.	2.
1.02	20.00	88	0.07	0.02	0.05	2798.	1.04	22.00	188	0.	0.	0.	2.
1.02	20.30	89	0.07	0.02	0.05	2405.	1.04	22.30	189	0.	0.	0.	2.
1.02	21.00	90	0.07	0.02	0.05	2019.	1.04	23.00	190	0.	0.	0.	2.
1.02	21.30	91	0.07	0.02	0.05	1673.	1.04	23.30	191	0.	0.	0.	2.
1.02	22.00	92	0.07	0.02	0.05	1384.	1.05	0.	192	0.	0.	0.	2.
1.02	22.30	93	0.07	0.02	0.05	1146.	1.05	0.30	193	0.	0.	0.	2.
1.02	23.00	94	0.07	0.02	0.05	950.	1.05	1.00	194	0.	0.	0.	2.
1.02	23.30	95	0.07	0.02	0.05	789.	1.05	1.30	195	0.	0.	0.	2.
1.03	0.	96	0.07	0.02	0.05	657.	1.05	2.00	196	0.	0.	0.	2.
1.03	0.30	97	0.	0.	0.	548.	1.05	2.30	197	0.	0.	0.	2.
1.03	1.00	98	0.	0.	0.	457.	1.05	3.00	198	0.	0.	0.	2.
1.03	1.30	99	0.	0.	0.	381.	1.05	3.30	199	0.	0.	0.	2.
1.03	2.00	100	0.	0.	0.	317.	1.05	4.00	200	0.	0.	0.	2.

SUM 21.02 17.41 3.61 47119.  
( 534.01 442.01 92.01 1334.26 )

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
3584.	2674.	963.	326.	47117.
101.	76.	27.	9.	1334.
	11.90	17.14	17.44	17.48
	302.35	435.26	442.85	443.89
	1326.	1909.	1942.	1947.
	1636.	2355.	2396.	2402.

CFS  
CMS  
INCHES  
MM  
AC-FT  
T-OLS CU M


#0VF#

# STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)		FOC.		1200.		1600.		2000.		2400.		2800.		3200.		3600.		PRECIP(L) AND EXCESS(X)		C.		C.		C.	
0.		400.		C.		0.		0.		0.		C.		0.		6.		C.		C.		C.		C.	
C.		0.		C.		0.		0.		0.		C.		0.		6.		C.		C.		C.		C.	
0.30	11																								
1.00	21																								
1.30	31																								
2.00	41																								
2.30	51																								
3.00	61																								
3.30	71																								
4.00	81																								
4.30	91																								
5.00	101																								
5.30	111																								
6.00	121																								
6.30	131																								
7.00	141																								
7.30	151																								
8.00	161																								
8.30	171																								
9.00	181																								
9.30	191																								
10.00	201																								
10.30	211																								
11.00	221																								
11.30	231																								
12.00	241																								
12.30	251																								
13.00	261																								
13.30	271																								
14.00	281																								
14.30	291																								
15.00	301																								
15.30	311																								
16.00	321																								
16.30	331																								
17.00	341																								
17.30	351																								
18.00	361																								
19.30	371																								
19.00	381																								
17.30	391																								
20.00	401																								
20.30	411																								
21.00	421																								
21.30	431																								
22.00	441																								
22.30	451																								
23.00	461																								
23.30	471																								
0.	481																								
0.30	491																								
1.00	501																								
1.30	511																								
2.00	521																								
2.30	531																								
3.00	541																								
3.30	551																								
4.00	561																								
4.30	571																								

LLX

0 571  
0 581  
0 591  
0 601  
0 611  
0 621  
0 631  
0 641  
0 651  
0 661  
0 671  
0 681  
0 691  
0 701  
0 711  
0 721  
0 731  
0 741  
0 751  
0 761  
0 771  
0 781  
0 791  
0 801  
0 811  
0 821  
0 831  
0 841  
0 851  
0 861  
0 871  
0 881  
0 891  
0 901  
0 911  
0 921  
0 931  
0 941  
0 951  
0 961  
0 971  
0 981  
0 991  
1001  
1011  
1021  
1031  
1041  
1051  
1061  
1071  
1081  
1091  
1101  
1111  
1121  
1131  
1141  
1151  
1161  
1171  
1181  
1191  
1201  
1211  
1221



14.001241  
14.301251  
15.001261  
15.301271  
16.001281  
16.301291  
17.001301  
17.301311  
18.001321  
18.301331  
19.001341  
19.301351  
20.001361  
20.301371  
21.001381  
21.301391  
22.001401  
22.301411  
23.001421  
23.301431  
0.1441  
0.301451  
1.001461  
1.301471  
2.001481  
2.301491  
3.001501  
3.301511  
4.001521  
4.301531  
5.001541  
5.301551  
6.001561  
6.301571  
7.001581  
7.301591  
8.001601  
8.301611  
9.001621  
9.301631  
10.001641  
10.301651  
11.001661  
11.301671  
12.001681  
12.301691  
13.001701  
13.301711  
14.001721  
14.301731  
15.001741  
15.301751  
16.001761  
16.301771  
17.001781  
17.301791  
18.001801  
18.301811  
19.001821  
19.301831  
20.001841  
20.301851  
21.001861  
21.301871  
22.001881  
22.301891

[illegible][illegible]








\*QVF\*

STATION 1







01153

[illegible]

STAGE	
1306.3	1306.4
1306.4	1306.5
1306.5	1306.6
1306.6	1306.7
1306.7	1306.8
1306.8	1306.9
1306.9	1307.0
1307.0	1307.1
1307.1	1307.2
1307.2	1307.3
1307.3	1307.4
1307.4	1307.5
1307.5	1307.6
1307.6	1307.7
1307.7	1307.8
1307.8	1307.9
1307.9	1308.0
1308.0	1308.1
1308.1	1308.2
1308.2	1308.3
1308.3	1308.4
1308.4	1308.5
1308.5	1308.6
1308.6	1308.7
1308.7	1308.8
1308.8	1308.9
1308.9	1309.0
1309.0	1309.1
1309.1	1309.2
1309.2	1309.3
1309.3	1309.4
1309.4	1309.5
1309.5	1309.6
1309.6	1309.7
1309.7	1309.8
1309.8	1309.9
1309.9	1310.0
1310.0	1310.1
1310.1	1310.2
1310.2	1310.3
1310.3	1310.4
1310.4	1310.5
1310.5	1310.6
1310.6	1310.7
1310.7	1310.8
1310.8	1310.9
1310.9	1311.0
1311.0	1311.1
1311.1	1311.2
1311.2	1311.3
1311.3	1311.4
1311.4	1311.5
1311.5	1311.6
1311.6	1311.7
1311.7	1311.8
1311.8	1311.9
1311.9	1312.0
1312.0	1312.1
1312.1	1312.2
1312.2	1312.3
1312.3	1312.4
1312.4	1312.5
1312.5	1312.6
1312.6	1312.7
1312.7	1312.8
1312.8	1312.9
1312.9	1313.0
1313.0	1313.1
1313.1	1313.2
1313.2	1313.3
1313.3	1313.4
1313.4	1313.5
1313.5	1313.6
1313.6	1313.7
1313.7	1313.8
1313.8	1313.9
1313.9	1314.0
1314.0	1314.1
1314.1	1314.2
1314.2	1314.3
1314.3	1314.4
1314.4	1314.5
1314.5	1314.6
1314.6	1314.7
1314.7	1314.8
1314.8	1314.9
1314.9	1315.0
1315.0	1315.1
1315.1	1315.2
1315.2	1315.3
1315.3	1315.4
1315.4	1315.5
1315.5	1315.6
1315.6	1315.7
1315.7	1315.8
1315.8	1315.9
1315.9	1316.0
1316.0	1316.1
1316.1	1316.2
1316.2	1316.3
1316.3	1316.4
1316.4	1316.5
1316.5	1316.6
1316.6	1316.7
1316.7	1316.8
1316.8	1316.9
1316.9	1317.0
1317.0	1317.1
1317.1	1317.2
1317.2	1317.3
1317.3	1317.4
1317.4	1317.5
1317.5	1317.6
1317.6	1317.7
1317.7	1317.8
1317.8	1317.9
1317.9	1318.0
1318.0	1318.1
1318.1	1318.2
1318.2	1318.3
1318.3	1318.4
1318.4	1318.5
1318.5	1318.6
1318.6	1318.7
1318.7	1318.8
1318.8	1318.9
1318.9	1319.0
1319.0	1319.1
1319.1	1319.2
1319.2	1319.3
1319.3	1319.4
1319.4	1319.5
1319.5	1319.6
1319.6	1319.7
1319.7	1319.8
1319.8	1319.9
1319.9	1320.0
1320.0	1320.1
1320.1	1320.2
1320.2	1320.3
1320.3	1320.4
1320.4	1320.5
1320.5	1320.6
1320.6	1320.7
1320.7	1320.8
1320.8	1320.9
1320.9	1321.0
1321.0	1321.1
1321.1	1321.2
1321.2	1321.3
1321.3	1321.4
1321.4	1321.5
1321.5	1321.6
1321.6	1321.7
1321.7	1321.8
1321.8	1321.9
1321.9	1322.0
1322.0	1322.1
1322.1	1322.2
1322.2	1322.3
1322.3	1322.4
1322.4	1322.5
1322.5	1322.6
1322.6	1322.7
1322.7	1322.8
1322.8	1322.9
1322.9	1323.0
1323.0	1323.1
1323.1	1323.2
1323.2	1323.3
1323.3	1323.4
1323.4	1323.5
1323.5	1323.6
1323.6	1323.7
1323.7	1323.8
1323.8	1323.9
1323.9	1324.0
1324.0	1324.1
1324.1	1324.2
1324.2	1324.3
1324.3	1324.4
1324.4	1324.5
1324.5	1324.6
1324.6	1324.7
1324.7	1324.8
1324.8	1324.9
1324.9	1325.0
1325.0	1325.1
1325.1	1325.2
1325.2	1325.3
1325.3	1325.4
1325.4	1325.5
1325.5	1325.6
1325.6	1325.7
1325.7	1325.8
1325.8	1325.9
1325.9	1326.0
1326.0	1326.1
1326.1	1326.2
1326.2	1326.3
1326.3	1326.4
1326.4	1326.5
1326.5	1326.6
1326.6	1326.7
1326.7	1326.8
1326.8	1326.9
1326.9	1327.0
1327.0	1327.1
1327.1	1327.2
1327.2	1327.3
1327.3	1327.4
1327.4	1327.5
1327.5	1327.6
1327.6	1327.7
1327.7	1327.8
1327.8	1327.9
1327.9	1328.0
1328.0	1328.1
1328.1	1328.2
1328.2	1328.3
1328.3	1328.4
1328.4	1328.5
1328.5	1328.6
1328.6	1328.7
1328.7	1328.8
1328.8	1328.9
1328.9	1329.0
1329.0	1329.1
1329.1	1329.2
1329.2	1329.3
1329.3	1329.4
1329.4	1329.5
1329.5	1329.6
1329.6	1329.7
1329.7	1329.8
1329.8	1329.9
1329.9	1330.0
1330.0	1330.1
1330.1	1330.2
1330.2	1330.3
1330.3	1330.4
1330.4	1330.5
1330.5	1330.6
1330.6	1330.7
1330.7	1330.8
1330.8	1330.9
1330.9	1331.0
1331.0	1331.1
1331.1	1331.2
1331.2	1331.3
1331.3	1331.4
1331.4	1331.5
1331.5	1331.6
1331.6	1331.7
1331.7	1331.8
1331.8	1331.9
1331.9	1332.0
1332.0	1332.1
1332.1	1332.2
1332.2	1332.3
1332.3	1332.4
1332.4	1332.5
1332.5	1332.6
1332.6	1332.7
1332.7	1332.8
1332.8	1332.9
1332.9	1333.0
1333.0	1333.1
1333.1	1333.2
1333.2	1333.3
1333.3	1333.4
1333.4	1333.5
1333.5	1333.6
1333.6	1333.7
1333.7	1333.8
1333.8	1333.9
1333.9	1334.0
1334.0	1334.1
1334.1	1334.2
1334.2	1334.3
1334.3	1334.4
1334.4	1334.5
1334.5	1334.6
1334.6	1334.7
1334.7	1334.8
1334.8	1334.9
1334.9	1335.0
1335.0	1335.1
1335.1	1335.2
1335.2	1335.3
1335.3	1335.4
1335.4	1335.5
1335.5	1335.6
1335.6	1335.7
1335.7	1335.8
1335.8	1335.9
1335.9	1336.0
1336.0	1336.1
1336.1	1336.2
1336.2	1336.3
1336.3	1336.4
1336.4	1336.5
1336.5	1336.6
1336.6	1336.7
1336.7	1336.8
1336.8	1336.9
1336.9	1337.0
1337.0	1337.1
1337.1	1337.2
1337.2	1337.3
1337.3	1337.4
1337.4	1337.5
1337.5	1337.6
1337.6	1337.7
1337.7	1337.8
1337.8	1337.9
1337.9	1338.0
1338.0	1338.1
1338.1	1338.2
1338.2	1338.3
1338.3	1338.4
1338.4	1338.5
1338.5	1338.6
1338.6	1338.7
1338.7	1338.8
1338.8	1338.9
1338.9	1339.0
1339.0	1339.1
1339.1	1339.2
1339.2	1339.3
1339.3	1339.4
1339.4	1339.5
1339.5	1339.6
1339.6	1339.7
1339.7	1339.8
1339.8	1339.9
1339.9	1340.0
1340.0	1340.1
1340.1	1340.2
1340.2	1340.3
1340.3	1340.4
1340.4	1340.5
1340.5	1340.6
1340.6	1340.7
1340.7	1340.8
1340.8	1340.9
1340.9	1341.0
1341.0	1341.1
1341.1	1341.2
1341.2	1341.3
1341.3	1341.4
1341.4	1341.5
1341.5	1341.6
1341.6	1341.7
1341.7	1341.8
1341.8	1341.9
1341.9	1342.0
1342.0	1342.1
1342.1	1342.2
1342.2	1342.3
1342.3	1342.4
1342.4	1342.5
1342.5	1342.6
1342.6	1342.7
1342.7	1342.8
1342.8	1342.9
1342.9	1343.0
1343.0	1343.1
1343.1	1343.2
1343.2	1343.3
1343.3	1343.4
1343.4	1343.5
1343.5	1343.6
1343.6	1343.7
1343.7	1343.8
1343.8	1343.9
1343.9	1344.0
1344.0	1344.1
1344.1	1344.2
1344.2	1344.3
1344.3	1344.4
1344.4	1344.5
1344.5	1344.6
1344.6	1344.7
1344.7	1344.8
1344.8	1344.9
1344.9	1345.0
1345.0	1345.1
1345.1	1345.2
1345.2	1345.3
1345.3	1345.4
1345.4	1345.5
1345.5	1345.6
1345.6	1345.7
1345.7	1345.8
1345.8	1345.9
1345.9	1346.0
1346.0	1346.1
1346.1	1346.2
1346.2	1346.3
1346.3	1346.4
1346.4	1346.5
1346.5	1346.6
1346.6	1346.7
1346.7	1346.8
1346.8	1346.9
1346.9	1347.0
1347.0	1347.1
1347.1	1347.2
1347.2	1347.3
1347.3	1347.4
1347.4	1347.5
1347.5	1347.6
1347.6	1347.7
1347.7	1347.8
1347.8	1347.9
1347.9	1348.0
1348.0	1348.1
1348.1	1348.2
1348.2	1348.3
1348.3	1348.4
1348.4	1348.5
1348.5	1348.6
1348.6	1348.7
1348.7	1348.8
1348.8	1348.9
1348.9	1349.0
1349.0	1349.1
1349.1	1349.2
1349.2	1349.3
1349.3	1349.4
1349.4	1349.5
1349.5	1349.6
1349.6	1349.7
1349.7	1349.8
1349.8	1349.9
1349.9	1350.0
1350.0	1350.1
1350.1	1350.2
1350.2	1350.3
1350.3	1350.4
1350.4	1350.5
1350.5	1350.6
1350.6	1350.7
1350.7	1350.8
1350.8	1350.9
1350.9	1351.0
1351.0	1351.1
1351.1	1351.2
1351.2	1351.3
1351.3	1351.4
1351.4	1351.5
1351.5	1351.6
1351.6	1351.7
1351.7	1351.8
1351.8	1351.9
1351.9	1352.0
1352.0	1352.1
1352.1	1352.2
1352.2	1352.3
1352.3	1352.4
1352.4	1352.5
1352.5	1352.6
1352.6	1352.7
1352.7	1352.8
1352.8	1352.9
1352.9	1353.0
1353.0	1353.1
1353.1	1353.2
1353.2	1353.3
1353.3	1353.4
1353.4	1353.5
1353.5	1353.6
1353.6	1353.7
1353.7	1353.8
1353.8	135

1325.7 1325.3 1324.9 1324.4 1324.0 1323.6 1319.4 1319.1 1318.8  
 1321.7 1321.0 1320.6 1320.3 1320.0 1319.7 1316.4 1316.4 1316.2  
 1318.5 1318.2 1317.9 1317.4 1317.2 1316.5 1316.7 1316.4 1316.2  
 1316.0 1315.8 1315.5 1315.1 1314.9 1314.7 1314.6 1314.4 1314.2  
 1314.0 1313.8 1313.7 1313.3 1313.2 1313.0 1312.9 1312.7 1312.6  
 1312.5 1312.2 1312.1 1311.9 1311.7 1311.6 1311.5 1311.4  
 1311.2 1311.0 1310.9 1310.8 1310.7 1310.6 1310.5 1310.4

PEAK OUTFLOW IS 3542. AT TIME 42.50 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
3542.	2644.	869.	321.	46463.
100.	75.	25.	9.	1316.
	11.77	15.82	17.15	17.23
	298.89	401.82	435.70	437.73
	1311.	1762.	1911.	1926.
	1617.	2174.	2357.	2368.

CFS  
 CMS  
 INCHES  
 MM  
 AC-FT  
 TPOUS CU M

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO EECNCHIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS	
				RATIO 1	RATIO 2
HYDROGRAPH AT	1	2.09	1	0.50	1.00
	(	0.00)	(	1792.	3584.
ROUTED TO	1	2.09	1	50.74)	101.43)
	(	0.00)	(	1746.	3542.
				49.45)	100.29)



# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1306.30 2. 0.	SPILLWAY CREST 1306.30 2. 0.	TCP OF DAM 1344.90 398. 9009.	
	MAXIMUM RESERVOIR ELEV	MAXIMUM DEPTH OVER JAM	MAXIMUM OUTFLOW CFS	DURATION EVER TCP HOURS	TIME OF MAX OUTFLOW HOURS
RATIO CF PIF	1342.91 1344.48	0. 0.	1746. 3542.	0. 0.	43.00 42.50
0.50 1.00					TIME OF FAILURE HOURS 0. 0.

APPENDIX D

STABILITY COMPUTATIONS

New York  
DEW

5-12

MILL BROOK - SITE 1

5-13-77

NY-2682-D

SLOPE STABILITY - Homogeneous fill

4-3

Borrow materials will consist of GM, SM, GM-GC from the emergency spillway excavation.

typically the materials are represented by samples by field samples 3.1, 203.1 & 206.1

These mat'ls contain:

42-45% Fines

LL = 18-25

24-41% Sands

PI = 1-9

25-35% Gravel

density - ASTM D-698, method A

$\gamma_d = 119.5 - 121.0$  pcf

@ cpt moisture = 11.5%

shear strength -

@ 95% of  $\gamma_d$

a. total stress :  $\phi = 12^\circ - 13.5^\circ$   
 $c = 325$  psf

b. effective stress :  $\phi = 30^\circ - 30.5^\circ$   
 $c = 125$  psf

CONDITION	Select embankment properties for slope stability					
	REQ'D F.S.	$\gamma_m$	$\gamma_{sat}$	$\gamma_{comp}$	$\phi$	$c$
1. Steady Seepage w/Seismic	1.5	133.2	137.1	74.7	$\phi' = 30^\circ, 13^\circ$	$c' = 125, 325$
	1.1	133.2	137.1	74.7	$\phi = 13^\circ$	$c = 325$
* 2. Drawdown w/Seismic	1.3	133.2	137.1	74.7	$\phi = 13^\circ$	$c = 325$
3. End of Constr	1.4	133.2	137.1	74.7	$\phi' = 30^\circ$	$c' = 125$

The structure is located Chenango County, N.Y. which is seismic zone I, therefore a seismic coefficient of 0.05 will be used.

(1234.7)

Drawdown will be assumed to take place from the 1% peak elev.

New York  
DEW

5-12  
Slope Stability

(DPU)

Mill Brook - Site 1

5-13-77

NY-2682-D

2

4-4

@ 95% of std.  $\gamma_d = 119.5\%$

95%  $\gamma_d = 113.5 \text{ pcf}$

let  $w$  be  $\pm 2\%$  or  $9.5\%$  to  $13.5\%$  ✓

$$\gamma_d = \frac{\gamma_m}{1+w}$$

$$\gamma_m = \gamma_d(1+w) = 119.5(1.115) = 133.2 \text{ pcf}$$

$$\text{for } \gamma_{\text{sat}} = W_s + W_{\text{wat}} = 119.5 + \gamma_{H_2O}$$

$$\text{and } V_s = \frac{W_s}{\gamma_w G_s} = \frac{119.5}{2.67(62.4)} = 0.717 \text{ ft}^3$$

@ 100% sat.  $V_w = 0.283$

$$\text{and } W_{\text{wat}} = 0.283(62.4) = 17.6 \text{ pcf}$$

$$\therefore \gamma_{\text{sat}} = 119.5 + 17.6 = 137.1 \text{ pcf}$$

$$\gamma_{\text{buoyant}} = 137.1 - 62.4 = 74.7$$

### Foundation soils

1. Soils are much the same as abutments  
outwash rather than fill where <sup>borings</sup> will be taken, densities are good. Therefore  
use the same soil properties as for the  
embankment. Surface ~~pre-consolidated~~ soils will be  
removed

ESTIMATED FOR ML-CL IN FOUNDATION  $\phi = 10^\circ$  (TOTAL)  $C = 400$   $\gamma_{\text{SAT}} 130$   
 $\phi = 25^\circ$   $C = 150$  (EEP)  $\gamma_{\text{buoy}} = 67.6$

2. Rock - shale and sandstone. For slope stability  
use a  $\phi = 50^\circ$ ,  $\gamma_{\text{sat}} = 160 \text{ pcf}$  and  $C = 2,000 \text{ psf}$

BASED ON ELOW COUNT DATA & PRECONSOLIDATED STATE OF  
MATERIAL USE  $\phi = 12^\circ$  (total)  $C = 600$  (7/11/77 (DPU))

NEW YORK MILL BROOK - SITE 1  
WALKER 8-29-77  
SLOPE STABILITY - UPSTREAM FACE - SUMMARY

NY-2682-D

4-7

UPSTREAM FACE.

DRAWDOWN FROM PERM POOL (ELEV 1307)

USING TOTAL STRESS PARAMETERS (CU)

$$\text{MIN FS} = 1.45 > \text{REQD } 1.3$$

$\therefore$  UPSTREAM FACE OK

NOTE:

FOR U.S. FACE WITH DRAWDOWN FROM  
100 WATER SURFACE ELEV (1334.7)

USING TOTAL STRESS (CU) PARAMETERS

FS = 1.16 WITH FAILURE SURFACE  
ENTIRELY WITHIN EMBANKMENT  
IN WHICH CASE AFS OF 1.2 IS ALLOW.

$$\therefore \text{FS } 1.16 \approx 1.2$$

THIS EMBANKMENT IS CONSIDERED STABLE  
BECAUSE OF LOW FREQUENCY OF OCCURRENCE  
OF HIGH WATER CONDITION

APPENDIX E

REFERENCES

## APPENDIX E

### REFERENCES

- 1) U.S. Department of Commerce, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May 1961.
- 2) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 3) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.
- 4) Elwyn E. Seelye, Design, 3rd edition, John Wiley and Sons, Inc., 1960
- 5) U.S. Department of the Interior, Bureau of Reclamation; Design of Small Dams, 2nd edition (rev. reprint), 1977.


APPENDIX F

DRAWINGS





VICINITY MAP  
MILL BROOK WATERSHED PROJECT  
SITE I  
NY-715






TOPOGRAPHIC MAP  
MILLBROOK WATERSHED PROJECT  
SITE 1  
NY 715

# CONSTRUCTION DETAILS

## LEGEND


- TEST PIT, LOGGED ONLY
- ⊙ TEST PIT, LOGGED & SAMPLED
- DRILL HOLE, LOGGED ONLY
- ⊙ DRILL HOLE, LOGGED & SAMPLED
- SEDIMENT POOL ELEV.
- DESIGN HIGH WATER ELEV.
- ⊗ FENCE LINE (EXISTING, TO BE REMOVED)
- /— FENCE LINE TO BE CONSTRUCTED
- △ TRANSIT HUB
- CONSTRUCTION LIMIT
- ▨ FOUNDATION EXCAVATION  
AVERAGE DEPTH - 3 FT.

- ✓1 WOODED AND BRUSH AREAS UNDER THE DAM AND LEVEE (INCLUDING 15 FEET OUTSIDE THE UPSTREAM AND DOWNSTREAM TOES) SHALL BE CLEARED AND GRUBBED
- ✓2 WOODED AND BRUSH AREAS UNDER THE EMERGENCY SPILLWAY, INCLUDING 15 FEET OUTSIDE THE CUT SLOPE, SHALL BE CLEARED AND GRUBBED
- ✓3 LIMITS TO BE CLEARED AND GRUBBED WILL BE STAKED IN THE FIELD BY THE ENGINEER
- ✓4 AREA UPSTREAM FROM THE DAM AND BELOW ELEVATION 1308 SHALL BE CLEARED
- ✓5 AREA 100 FEET WIDE LEADING TO THE EMERGENCY SPILLWAY FROM THE SEDIMENT POOL SHALL BE CLEARED
- ✓6 WASTE AREA, ACCESS ROAD, AND PRINCIPAL SPILLWAY OUTLET SHALL BE CLEARED
- ✓7 LIMITS TO BE CLEARED WILL BE STAKED IN THE FIELD BY THE ENGINEER
- ✓8 DEPTHS AND LIMITS OF BORROW EXCAVATION WILL BE DETERMINED IN THE FIELD BY THE ENGINEER
- ✓9 AT COMPLETION OF EARTH FILL OPERATIONS, THE BORROW AND WASTE AREAS SHALL BE LEFT GENTLY SLOPING, GENERALLY SMOOTH AND FREE-DRAINING
- ✓10. BOTTOM SECTION OF THE EMERGENCY SPILLWAY SHALL BE COVERED WITH 6 INCHES OF TOPSOIL THROUGH ENTIRE LENGTH



## QUANTITIES

PEP MODIFICATION NO. 6  
EXCAVATION  
EMBANKMENT 1500 CY  
24" DIA CULVERT PIPE 84 LF



15 FEET  
 GRADED AND GRUBBED  
 INCLUDING 15 FEET

FIELD

ALL BE

THE SEDIMENT

ALL BE CLEARED

ENGINEER

ED IN THE

WASTE SPEAS

-DRAINING

ED WITH 5

40' 24" DIA  
 CULVERT  
 +84

CONSTRUCTION  
 LIMIT LINE

TIES

ATION NO. 5

1500 CY

RPE 84 LF

1343.1



LIMIT OF  
 FOUNDATION  
 EXCAVATION  
 (SEE NEXT SHEET)

SEDIMENT POOL  
 ELEV. 1306.5

WASTE  
 AREA

EACH ACCESS ROAD  
 CONSTRUCTION  
 STA 2+60

BH#2 ELEV. 1328.23 DOUBLE HEADED NAIL + S.C. DISC 3' UP  
 FROM BASE IN 6" SUGAR MAPLE  
 BH#3A ELEV. 1314.16 DOUBLE HEADED NAIL + S.C. DISC IN  
 12" PEP LAR 2' ABOVE THE GROUND, SOUTH  
 SIDE OF TREE, UPSIDE OF 7th C&LT. ASOT  
 BH#10 ELEV. 1307.88 DOUBLE HEADED NAIL + S.C. DISC. IN  
 TOP OF 8" YELLOW B-CH STUMP D&S SIDE  
 OF DIRT ON LT. ASOT.



AS BUILT  
 9-13-79

0 50 100 200  
 SCALE IN FEET

MILLBROOK WATERSHED PROJECT


FLOODWATER RETARDING DAM NO. 1  
 CHENANGO COUNTY NEW YORK  
 PLAN OF STORAGE AREA


U.S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE

D. WALKER C/77

WAR 771 NY-2602-P

2





**LEGEND**

SEE SHEET 2


**FOUNDATION EXCAVATION**

✓ EXCAVATE THE SATURATED, BLACK ORGANIC SOIL AS REPRESENTED BY DH-353A FROM UNDER THE DAM. SEE SHEET 5

CLEARING	2.5 AC
CLEARING + GRUBBING	3.4 AC
SEEDING + TIE-DOWN	13.4 AC

**MILLBROOK WATERSHED PROJECT**  
 FLOODWATER RETARDING DAM NO. 1  
 CHEMANGO COUNTY, NEW YORK  
 PLAN OF STRUCTURAL WORKS  
 U.S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE

D. WALKER 6-77  
 DJ. ANGLIO 7-77  
 W.A.R. 7-77  
 3. NY-2002-P




1360

1340

1320

1300



0 2 4 8 16  
VERT SCALE IN FEET

0 10 20 40 80  
HORIZ SCALE IN FEET

3+00

4+00


5+00

6+00

7+00

8+00

CUTOFF TRENCH



AS BUILT

9/13/79



MILLBROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 1  
CHENANGO COUNTY NEW YORK  
CUTOFF TRENCH EXCAVATION  
DEPARTMENT OF TRANSPORTATION  
NEW YORK STATE

D WALKER 4-77  
D ANGELO 7-77  
WAR 7-77

NY-2682-P










2

# DAM PLAN VIEW




1350

1330

1310

1290

APPROX EXISTING  
GROUND LINE



PERFORATED  
PIPE 6" DIA. W/ELB  
CAP S: 0.005 FT/FT  
ELEV. 1297.1


C OF OUTLET PIPE, 6" DIA  
INV. ELEV. 1296.7

C OF PRINCIPAL SPILLWAY

C OF OUTLET PIPE, 6" DIA  
INV. ELEV. 1296.7

TOP OF CHIMNEY DRAIN 1310.0

PROFILE ALONG C OF DRAIN  
(LOOKING DOWNSTREAM)



**DRAINAGE SYSTEM DETAILS**

1. DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

2. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

3. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

4. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

5. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

6. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

7. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

8. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.


9. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.

10. THE DRAINAGE SYSTEM SHALL BE DESIGNED TO REMOTE EXCESS WATER FROM THE ROADWAY AND ADJACENT AREAS TO THE FLOODWATER RETARDING DAM NO. 1.


1256.7  
1256.7  
1256.7  
1256.7  
1256.7  
1256.7  
1256.7  
1256.7  
1256.7  
1256.7

TABLE 103.4

SCREEN SIZE	PASSING
1/2"	0.15
1/4"	0.10
1/8"	0.05



ABUTMENT DRAIN BEYOND CHIMNEY DRAIN




AS BUILT 800 9/13/79

MILLBROCK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO. 1  
CHENANGO COUNTY, NEW YORK  
DRAINAGE SYSTEM  
U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE




WALKER 6-77  
PAO CONST. 1-77  
COH 6-77  
NY-2082-P

7100

2





0 2 4 8  
SCALE IN FT



SMALL ANIMAL RODENTS  
EXCLUDED

2



13 000

9/13/78

MILLBROOK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 1  
CHEMANGO COUNTY, NEW YORK  
DRAINAGE SYSTEM

U S DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

DESIGNED BY	D. WALKER	6-7-78
CHECKED BY	CDM	6-7-78
DATE	9-13-78	
PROJECT NO.	NY-2032-P	





2


JOINT	DISTANCE FROM OUTLET	INVERT OF 30" DIAMETER PIPE	GRADE SET
OUTLET	0	1294.75	1294.77
J1	20	1294.94	1294.97
J2	40	1295.13	1295.12
J3	60	1295.32	1295.33
J4	80	1295.51	1295.52
J5	100	1295.71	1295.73
J6	120	1295.90	1295.90
J7	140	1296.09	1296.09
J8	160	1296.28	1296.33
J9	180	1296.47	1296.52
J10	200	1296.66	1296.67
J11	220	1296.85	1296.87
J12	240	1297.04	1297.06
J13	260	1297.24	1297.26
J14	280	1297.43	1297.45
J15	300	1297.62	1297.63
RISER	340	1298.00	1298.02

ABOVE DIMENSIONS FOR LENGTHS OF PIPE ARE BASED ON  
NOMINAL LENGTHS AND DO NOT INCLUDE CREEP

COLLAR	DISTANCE FROM OUTLET	INVERT OF 30" DIAMETER PIPE
I	190	1296.57
II	210	1296.75
III	230	1296.95
IV	250	1297.14
V	270	1297.33
VI	290	1297.52
VII	310	1297.72
VIII	330	1297.90

WHEN PIPE IS SUPPLIED IN LENGTHS OTHER THAN SHOWN,  
THE ENGINEER WILL PROVIDE THE CONTRACTOR WITH  
A REVISION OF THIS SHEET








4 OF DRAIN P.TE  
DETAIL SMT 8

3017 110104

SECRET

4 OF 20200726 25:11 2.7.20

### PLAN OF PRINCIPAL SPILLWAY AND PLUNGE POOL



APPROX EXISTING GROUND LINE


- 357 1294 0

549


1255.

## SECTION


CENTERLINE PROFILE OF PRINCIPAL  
SPILLWAY AND PLUNGE POOL



2





SECTION A-A as shown



1. THE STATE OF TEXAS, COUNTY OF DALLAS  
 do hereby certify that the within and foregoing is a true and correct copy of the original as the same appears from the records of the County of Dallas, State of Texas.  
 IN WITNESS WHEREOF, I have hereunto set my hand and the seal of said County, at Dallas, Texas, this 10th day of May, 1907.


WILLAMETTE WATERSHED PROJECT  
FOURTH INTERIM REPORT, 1971  
CLATSOP COUNTY, OREGON  
PLANNING AND ECONOMIC DEVELOPMENT  
U.S. DEPARTMENT OF AGRICULTURE  
NATIONAL WATER RESEARCH INSTITUTE



FILL MATERIALS				EQUIPMENT	
MAX. SIZE	MAX. W. OF	MAX. L. OF	MAX. T. OF	MAX. W. OF	MAX. L. OF
1/2"	1/2"	1/2"	1/2"	1/2"	1/2"
1/4"	1/4"	1/4"	1/4"	1/4"	1/4"
3/8"	3/8"	3/8"	3/8"	3/8"	3/8"
1/2"	1/2"	1/2"	1/2"	1/2"	1/2"
3/4"	3/4"	3/4"	3/4"	3/4"	3/4"
1"	1"	1"	1"	1"	1"
1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	1 1/2"
2"	2"	2"	2"	2"	2"
2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"
3"	3"	3"	3"	3"	3"
3 1/2"	3 1/2"	3 1/2"	3 1/2"	3 1/2"	3 1/2"
4"	4"	4"	4"	4"	4"
4 1/2"	4 1/2"	4 1/2"	4 1/2"	4 1/2"	4 1/2"
5"	5"	5"	5"	5"	5"
5 1/2"	5 1/2"	5 1/2"	5 1/2"	5 1/2"	5 1/2"
6"	6"	6"	6"	6"	6"
6 1/2"	6 1/2"	6 1/2"	6 1/2"	6 1/2"	6 1/2"
7"	7"	7"	7"	7"	7"
7 1/2"	7 1/2"	7 1/2"	7 1/2"	7 1/2"	7 1/2"
8"	8"	8"	8"	8"	8"
8 1/2"	8 1/2"	8 1/2"	8 1/2"	8 1/2"	8 1/2"
9"	9"	9"	9"	9"	9"
9 1/2"	9 1/2"	9 1/2"	9 1/2"	9 1/2"	9 1/2"
10"	10"	10"	10"	10"	10"


1. THE PLACEMENT SHALL BE DONE BY HAND OR BY MEANS OF A CONCRETE PLACER.
2. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
3. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
4. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
5. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
6. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
7. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
8. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
9. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
10. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.

1. THE PLACEMENT SHALL BE DONE BY HAND OR BY MEANS OF A CONCRETE PLACER.
2. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
3. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
4. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
5. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
6. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
7. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
8. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
9. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.
10. THE PLACEMENT SHALL BE DONE IN LAYERS NOT THICKER THAN 12 INCHES.



1





PLAN - TOP


MANHOLE ASSEMBLY DETAIL

Circular Manhole Assembly 18" Dia.  
Clear Opening 30" Dia. (See Drawing  
Co. Model P-6451-HR 11-11-55)  
Steel Cap Screws, or Equivalent

The Lifting Device Shall Consist of a  
Hook at One Edge of the Lid and a  
Perimeter of the Lid

The Locking Device Shall Consist of a  
Hook at One Edge of the Lid and a  
and a Raising Bar With a Hex Bolt  
at the opposite edge

(See 13063-100, 13063-101)



SECTION A-A

1/4" x 6" Carbon steel  
to conform to Spec. 55.  
Continuous Thru Center  
Splices Shall Be Welded  
1/2" Welded  
2" Welded  
1/2" Welded



# NATURAL DESCRIPTIONS

**A**  
Gravel - silty, poorly graded - 10" max. size, usually 1/2", varied lithology; approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; wet to sat. rated; rapid permeability; (D.S. 1.1, G-C)

**B**  
Gravel, silty-sandy - 10" max. size, varied lithology; approx. 15% gravel, 85% matrix (which is approx. 15-40% gravel, 55-11% sand, and 4-40% non-plastic fines); brown; wet to sat. rated; rapid permeability; (D.S. 1.1, G-C)

**C**  
Silt, silty - 10" max. size, varied lithology; 15-40% gravel, 55-11% sand, and 4-40% non-plastic fines; brown; wet to sat. rated; rapid permeability; (D.S. 1.1, G-C)

**D**  
Silt, silty-sandy and gravel - 10" max. size; 10% gravel, 90% matrix (which is approx. 15% gravel, 55% sand and 30% non-plastic fines); brown; wet to sat. rated; rapid permeability; (D.S. 1.1, G-C)

**E**  
Topsoil - gravel, sand and silt w/roots and organic materials; brown; moist; permeability; loose; are (D.S. 1.1, G-C)

**F**  
Gravel - silty, poorly graded - 10" max. size, usually 1/2", varied lithology; approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; wet to sat. rated; rapid permeability; (D.S. 1.1, G-C)

**G**  
Silt, silty-sandy and gravel - 10" max. size; 10% gravel, 90% matrix (which is approx. 15% gravel, 55% sand and 30% non-plastic fines); brown; wet to sat. rated; rapid permeability; (D.S. 1.1, G-C)

## TP #1, Centerline of Box 5/8/60, PM, 1312.1

0.0 - 1.0 Topsoil  
1.0 - 9.0 Gravel - sandy, silty  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; wet to sat. rated; rapid permeability; loose; lacustrine; (D.S. 1.1 (SM))  
9.0 - 12.0 Sand - silty, w/gravel  
10% max.  
100% matrix (which is approx. 15% gravel, 85% sand and 10% non-plastic fines)  
Brown; moist; slight to moderately permeable; loose; lacustrine; (D.S. 1.1 (SM))  
12.0 - 15.0 Gravel - sandy, silty  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; wet to sat. rated; rapid permeability; loose; lacustrine; (D.S. 1.1 (SM))  
Note: Test pit dug partially in left abutment and partially in flood plain; heavy seepage @ 5.0 ft.

## TP #2, Centerline of Box 5/8/60, PM, 1314.1

0.0 - 0.5 Topsoil  
0.5 - 10.0 Gravel - sandy, silty, poorly graded  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; wet to sat. rated; rapid permeability; loose; alluvial gravel and sand; lacustrine; (D.S. 1.1 (G-C))  
Note: Pit walls curve in readily; heavy seepage @ 2.0 ft.; Pit abandoned @ 10.0 ft. due to caving and excess water; no indication of any change in material. Water level @ 4.0 ft.

## TP #3, Centerline of Box 5/8/60, PM, 1317.5

0.0 - 1.0 Topsoil  
1.0 - 15.0 Gravel - silty, sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))  
Note: Fill color has become darker due to caving; no indication of any change in material. Water level @ 4.0 ft.

## TP #4, Centerline of Box 5/8/60, PM, 1319.2

0.0 - 1.0 Topsoil  
1.0 - 15.0 Gravel - silty, sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))

## TP #5, Centerline of Box 5/8/60, PM, 1321.0

0.0 - 1.0 Topsoil  
1.0 - 15.0 Gravel - silty, sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))

## TP #6, Centerline of Box 5/8/60, PM, 1323.0

0.0 - 1.0 Topsoil  
1.0 - 14.0 Gravel - silty, sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))

14.0 - 15.0 Gravel - silty, sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))

## TP #7, Centerline of Box 5/8/60, PM, 1325.0

0.0 - 0.5 Topsoil  
0.5 - 5.0 Gravel - sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))  
9.0 - 12.0 Sand - silty, w/gravel  
10% max.  
100% matrix (which is approx. 15% gravel, 85% sand and 10% non-plastic fines)  
Brown; moist; slight to moderately permeable; loose; lacustrine; (D.S. 1.1 (SM))  
12.0 - 15.0 Gravel - sandy, silty  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; wet to sat. rated; rapid permeability; loose; lacustrine; (D.S. 1.1 (SM))  
Note: Test pit dug partially in left abutment and partially in flood plain; heavy seepage @ 5.0 ft.

## TP #8, Centerline of Box 5/8/60, PM, 1327.0

0.0 - 0.5 Topsoil  
0.5 - 5.5 Gravel - sandy  
18" max. - varied shape and lithology  
Approx. 15% gravel, 85% matrix (which is approx. 60% gravel, 40% sand and 10% non-plastic fines); brown; moist; slightly permeable; lacustrine; (D.S. 1.1 (SM))  
Note: Test pit dug partially in left abutment and partially in flood plain; heavy seepage @ 5.0 ft.

1

72-1000-1000, 1000, 1000

0.0 - 0.5 Topsoil

0.5 - 5 Gravel - sandy, silty  
13" max. - varied shape and lithology  
approx. 55% 5-16, 90% matrix (which is approx.  
40% gravel, 40% sand and 10% non-plastic fines)  
Gray brown, very rapidly permeable, loose, alluvial  
gravel, subsoil: GM

5.0 - 6.0 Bedrock

72-1000-1000, 1000, 1000

0.0 - 1.5 Alluvial silt w/rock and peat

1.5 - 5.0 Gravel - sandy, silty  
13" max. - varied shape and lithology  
approx. 55% 5-16, 90% matrix (which is approx.  
40% gravel, 40% sand and 10% non-plastic fines)  
Brown, saturated, rapidly permeable, loose, alluvial  
gravel, subsoil: GM

Note: CUL @ ground surface

72-1000-1000, 1000, 1000

0.0 - 0.5 Topsoil

0.5 - 5.0 Gravel - sandy, silty  
13" max. - varied shape and lithology  
approx. 55% 5-16, 90% matrix (which is approx.  
40% gravel, 40% sand and 10% non-plastic fines)  
Brown, saturated, rapidly permeable, loose, alluvial  
gravel, subsoil: GM

Note: Material is moist in upper portion of test  
pit; contains 10-20% fines. Water level @  
4.0 ft.

# LEGEND

## TEST HOLE NUMBERING SYSTEM

Test Pit	TP	Drill Hole	TH
Location of test	1-1-1	1-1-1	1-1-1
Test Area	1-1-1	1-1-1	1-1-1
Shoreline	1-1-1	1-1-1	1-1-1
Centerline of	1-1-1	1-1-1	1-1-1
Outlet Structure	1-1-1	1-1-1	1-1-1
Outlet Channel	1-1-1	1-1-1	1-1-1
Drain Line	1-1-1	1-1-1	1-1-1
Other	1-1-1	1-1-1	1-1-1

## UNIFIED SOIL CLASSIFICATION SYSTEM (USCS) SYMBOLS

- GW Well-sorted gravels and sands, highly permeable
- GP Poorly-sorted gravels
- GM Silty gravels, gravel-sand-silt mixtures
- GC Clayey gravels, gravel-sand-clay mixtures
- SW Well-sorted sands; non-plastic
- SP Poorly-sorted sands
- SM Silty sand; sand-silt mixtures
- SC Clayey sand; sand-clay mixtures
- ML Silts; silty, fine sand; sand-silt mixtures
- CL Clays of low to medium plasticity; silty, sand, or gravelly clay
- CH Clays of high plasticity; fat clays
- OH Organic silts or clays of medium to high plasticity
- OL Organic silts and organic silty clays of low plasticity
- OH Organic clays or silts of medium to high plasticity

## II Unified Classification by visual inspection in the field

## (III) Unified Classification by laboratory analysis

## Key to Drill Hole (TH) Logs

TH	TH	Material (USCS)	Depth (ft)
1	1	Well-sorted, fine sand, highly permeable	0.0 - 0.5
2	2	Drill hole to advance hole to water level	0.5 - 1.0
3	3	Hole advanced to water level	1.0 - 1.5
4	4	Rock core, 1.5" diameter	1.5 - 2.0
5	5	Percent rock core recovery - each drill run / 100	2.0 - 2.5
6	6	Permeability test (sp) - 1	2.5 - 3.0

100 - Rock core, 1.5" diameter

100 - Percent rock core recovery - each drill run / 100

100 - Permeability test (sp) - 1





BH #328 (continued)		19.0
115	Gravel - silty, clayey	
116	Gravel - silty, clayey	
117	Gravel - silty, clayey	
118	Gravel - silty, clayey	
119	Gravel - silty, clayey	
120	Gravel - silty, clayey	
121	Gravel - silty, clayey	
122	Gravel - silty, clayey	
123	Gravel - silty, clayey	
124	Gravel - silty, clayey	
125	Gravel - silty, clayey	
126	Gravel - silty, clayey	
127	Gravel - silty, clayey	
128	Gravel - silty, clayey	
129	Gravel - silty, clayey	
130	Gravel - silty, clayey	
131	Gravel - silty, clayey	
132	Gravel - silty, clayey	
133	Gravel - silty, clayey	
134	Gravel - silty, clayey	
135	Gravel - silty, clayey	
136	Gravel - silty, clayey	
137	Gravel - silty, clayey	
138	Gravel - silty, clayey	
139	Gravel - silty, clayey	
140	Gravel - silty, clayey	
141	Gravel - silty, clayey	
142	Gravel - silty, clayey	
143	Gravel - silty, clayey	
144	Gravel - silty, clayey	
145	Gravel - silty, clayey	
146	Gravel - silty, clayey	
147	Gravel - silty, clayey	
148	Gravel - silty, clayey	
149	Gravel - silty, clayey	
150	Gravel - silty, clayey	
151	Gravel - silty, clayey	
152	Gravel - silty, clayey	
153	Gravel - silty, clayey	
154	Gravel - silty, clayey	
155	Gravel - silty, clayey	
156	Gravel - silty, clayey	
157	Gravel - silty, clayey	
158	Gravel - silty, clayey	
159	Gravel - silty, clayey	
160	Gravel - silty, clayey	
161	Gravel - silty, clayey	
162	Gravel - silty, clayey	
163	Gravel - silty, clayey	
164	Gravel - silty, clayey	
165	Gravel - silty, clayey	
166	Gravel - silty, clayey	
167	Gravel - silty, clayey	
168	Gravel - silty, clayey	
169	Gravel - silty, clayey	
170	Gravel - silty, clayey	
171	Gravel - silty, clayey	
172	Gravel - silty, clayey	
173	Gravel - silty, clayey	
174	Gravel - silty, clayey	
175	Gravel - silty, clayey	
176	Gravel - silty, clayey	
177	Gravel - silty, clayey	
178	Gravel - silty, clayey	
179	Gravel - silty, clayey	
180	Gravel - silty, clayey	
181	Gravel - silty, clayey	
182	Gravel - silty, clayey	
183	Gravel - silty, clayey	
184	Gravel - silty, clayey	
185	Gravel - silty, clayey	
186	Gravel - silty, clayey	
187	Gravel - silty, clayey	
188	Gravel - silty, clayey	
189	Gravel - silty, clayey	
190	Gravel - silty, clayey	
191	Gravel - silty, clayey	
192	Gravel - silty, clayey	
193	Gravel - silty, clayey	
194	Gravel - silty, clayey	
195	Gravel - silty, clayey	
196	Gravel - silty, clayey	
197	Gravel - silty, clayey	
198	Gravel - silty, clayey	
199	Gravel - silty, clayey	
200	Gravel - silty, clayey	

Note: BH #328, 5/27/69

BH #329, Prin. Spgr., 5/27/69, BH, 1204.1		0.0
A	SH	Sand and gravel
F	SH	Shale; refusal on solid rock 57.0 ft.

BH #330, Prin. Spgr., 5/27/69, BH, 1202.9		0.0
A	SH	Sand and gravel
F	SH	Shale; refusal on solid rock 81.5 ft.

Continued

BH #331, 3rd Sta., 5/12/69, BH, 1209.8		0.0
B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines
42	SH	Gravel - silty, clayey
43	SH	Gravel - silty, clayey
44	SH	Gravel - silty, clayey
45	SH	Gravel - silty, clayey
46	SH	Gravel - silty, clayey
47	SH	Gravel - silty, clayey
48	SH	Gravel - silty, clayey
49	SH	Gravel - silty, clayey
50	SH	Gravel - silty, clayey

BH #332, 3rd Sta., 5/12/69, BH, 1209.8		0.0
C	SH	Sand-silty
71	SH	Approx. 10% gravel, 10% sand, 10% slightly plastic fines
72	SH	Gravel - silty, clayey
73	SH	Gravel - silty, clayey
74	SH	Gravel - silty, clayey
75	SH	Gravel - silty, clayey
76	SH	Gravel - silty, clayey
77	SH	Gravel - silty, clayey
78	SH	Gravel - silty, clayey
79	SH	Gravel - silty, clayey
80	SH	Gravel - silty, clayey

BH #333, 3rd Sta., 5/12/69, BH, 1209.8		0.0
B	SH	Gravel - silty, clayey
46	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines
47	SH	Gravel - silty, clayey
48	SH	Gravel - silty, clayey
49	SH	Gravel - silty, clayey
50	SH	Gravel - silty, clayey
51	SH	Gravel - silty, clayey
52	SH	Gravel - silty, clayey
53	SH	Gravel - silty, clayey
54	SH	Gravel - silty, clayey
55	SH	Gravel - silty, clayey

Note: Color of soil changes to gray brown 40.0 ft. and to gray 43.0 ft.

BH #334, 3rd Sta., 5/12/69, BH, 1209.8		0.0
E	SH	Topsoil

BH #335, 3rd Sta., 5/12/69, BH, 1209.8		0.0
A	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines
42	SH	Gravel - silty, clayey
43	SH	Gravel - silty, clayey
44	SH	Gravel - silty, clayey
45	SH	Gravel - silty, clayey
46	SH	Gravel - silty, clayey
47	SH	Gravel - silty, clayey
48	SH	Gravel - silty, clayey
49	SH	Gravel - silty, clayey
50	SH	Gravel - silty, clayey

BH #336, 3rd Sta., 5/12/69, BH, 1209.8		0.0
B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines
42	SH	Gravel - silty, clayey
43	SH	Gravel - silty, clayey
44	SH	Gravel - silty, clayey
45	SH	Gravel - silty, clayey
46	SH	Gravel - silty, clayey
47	SH	Gravel - silty, clayey
48	SH	Gravel - silty, clayey
49	SH	Gravel - silty, clayey
50	SH	Gravel - silty, clayey

BH #337, 3rd Sta., 5/12/69, BH, 1209.8		0.0
F	SH	Sandy shale w/ some small interbedded sandstone layers; fine grained; moderately weathered; gray; moderately hard, thin bedded; small fracture some approx. 15.0x15.0" sh

Note: BH #337

BH #338, 3rd Sta., 5/12/69, BH, 1209.8		0.0
E	SH	Topsoil - silty, gravelly
41	SH	Gravel - silty, clayey
42	SH	Gravel - silty, clayey
43	SH	Gravel - silty, clayey
44	SH	Gravel - silty, clayey
45	SH	Gravel - silty, clayey
46	SH	Gravel - silty, clayey
47	SH	Gravel - silty, clayey
48	SH	Gravel - silty, clayey
49	SH	Gravel - silty, clayey
50	SH	Gravel - silty, clayey

BH #339, 3rd Sta., 5/12/69, BH, 1209.8		0.0
B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines
42	SH	Gravel - silty, clayey
43	SH	Gravel - silty, clayey
44	SH	Gravel - silty, clayey
45	SH	Gravel - silty, clayey
46	SH	Gravel - silty, clayey
47	SH	Gravel - silty, clayey
48	SH	Gravel - silty, clayey
49	SH	Gravel - silty, clayey
50	SH	Gravel - silty, clayey

BH #340, 3rd Sta., 5/12/69, BH, 1209.8		0.0
--	--	-----

E	SH	Organic soil
41	SH	Gravel - silty, clayey

B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines

F	SH	Shale
41	SH	Gravel - silty, clayey

BH #341, 3rd Sta., 5/12/69, BH, 1209.8		0.0
--	--	-----

E	SH	Topsoil - silty, gravelly
41	SH	Gravel - silty, clayey

B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines

F	SH	Shale
41	SH	Gravel - silty, clayey

BH #342, 3rd Sta., 5/12/69, BH, 1209.8		0.0
--	--	-----

A	SH	Earth boring, probing for rock.
41	SH	Gravel - silty, clayey

F	SH	Sandy shale w/ some small interbedded sandstone layers; fine grained; moderately weathered; gray; moderately hard, thin bedded; small fracture some 15.0 x 15.0" sh
---	----	---

BH #343, 3rd Sta., 5/12/69, BH, 1209.8		0.0
--	--	-----

E	SH	Topsoil
41	SH	Gravel - silty, clayey

B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines

F	SH	Shale
41	SH	Gravel - silty, clayey

BH #344, 3rd Sta., 5/12/69, BH, 1209.8		0.0
--	--	-----

E	SH	Topsoil
41	SH	Gravel - silty, clayey

B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines

F	SH	Shale
41	SH	Gravel - silty, clayey

BH #345, 3rd Sta., 5/12/69, BH, 1209.8		0.0
--	--	-----

E	SH	Topsoil
41	SH	Gravel - silty, clayey

B	SH	Gravel - silty, clayey
41	SH	Approx. 10% gravel, 10% sand, 40% slightly plastic fines

F	SH	Shale
41	SH	Gravel - silty, clayey

SEE SHEET 2 OF 24 FOR LOCATIONS OF DRILL HOLES AND TEST PITS

13 JUL  
5/13/79

MILL BROOK WATERSHED PROJECT  
SITE 1  
DRILLING COUNTY NEW YORK  
LOGS OF TEST HOLES  
U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

2

TP #131. S.E. Corner Barron 4/13/77 B.Y. 1353 B

0.0' - 1.0' Topsoil

E

1.0' - 10.0' Gravel-sand-clay mixture

B

12" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
27% gravel, 24% sand, 49% slightly plastic fines)  
Brown, moist, slightly permeable, stiff, glacial till  
SC

O.S. 131.1 (25)

Note: Topsoil depth 1.0'

TP #231. E. End Along E. Emer. Drill 4/13/77 B.Y. 1341 B

1.0' - 11.0' Gravel-sand-clay mixture

B

12" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
27% gravel, 24% sand, 49% slightly plastic fines)  
Brown, moist, slightly permeable, stiff, glacial till,  
SC

Note: Topsoil depth 1.0'

TP #232. S.E. Side of Emer. Drill 4/13/77 B.Y. 1355 B

1.0' - 13.0' Gravel-sand-clay mixture

B

12" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
27% gravel, 24% sand, 49% slightly plastic fines)  
Brown, moist, slightly permeable, stiff, glacial till  
SC

Note: Topsoil depth 1.0'

TP #331. E. End Prim. Drill 4/13/77 B.Y. 1235 B

1.0' - 3.5' Silty gravels

A

5" - 8" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
50% gravel, 24% sand, 13% fines)  
Dark brown, wet, moderately permeable, medium, flood plain,  
GM-GC

3.5' - 7.0' Clayey silts

G

4" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
15% gravel, 12% sand, 73% low plasticity)  
Gray, moist, very slight permeability, very stiff,  
glacial till, ML-CL

7.0' - 11.5' Silty gravels

A

5" max.  
Approx. 50-60% 100 3-5" 75% matrix (which is approx  
50% gravel, 24% sand, 13% fines)  
Brown, very wet, rapid permeability, loose, glacial  
till, GM-GC

11.5' - 14.0' Clayey silts

G

4" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
15% gravel, 12% sand, 73% low plasticity)  
Gray, moist, very slightly permeable, very stiff,  
glacial till, ML-CL

Note: Topsoil depth 1.0'. Seepage in gravel layer  
below 7.0'. Bedrock @ 14.0'.

TP #531. N. Side Drain Line 4/13/77 B.Y. 1239 B

1.0' - 3.0' Clayey silts

G

12" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
15% gravel, 12% sand, 73% low plasticity)  
Gray, moist, very slightly permeable, very stiff, glacial  
till, ML-CL

Note: Rock depth 1.0'. This area has surfaces with seeps  
soft and sticky

3.0' - Very firm till

TP #532. S. Side Drain Line 4/13/77 B.Y. 1237 A

1.0' - 3.0' Silty gravels

A

5" - 8" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
50% gravel, 24% sand, 13% fines)  
Dark brown, wet, moderately permeable, medium, flood plain,  
GM-GC; O.S. 532.1 (23-24)

3.0' - 3.0' Clayey silts

G

3" - 5" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
15% gravel, 12% sand, 73% low plasticity)  
Gray, moist, very slightly permeable, very stiff, glacial  
till, ML-CL, O.S. 532.2 (21-22)

Note: Topsoil depth 1.0'. Seepage @ 1.5'

TP #533. S. End Drain Line 4/13/77 B.Y. 1313 B

1.0' - 11.0' Gravel-sand-clay mixture

B

12" max.  
Approx. 50-60% 100 3-5" 85% matrix (which is approx  
27% gravel, 24% sand, 49% slightly plastic fines)  
Brown, moist, slightly permeable, stiff, glacial till,  
SC

Note: Topsoil depth 1.0'

7

1299 3

SS matrix (which is approx  
slightly plastic fines)  
permeable, very st "f" 2' to 3' 11"

this area has surface water seeps

1297 4

SS matrix (which is approx  
fine, fine)  
permeable, "medium" 100 to 300  
1)

SS matrix (which is approx  
fine, plasticity fines,  
permeable, very st "f" glacial  
(CL-CL)

water seepage, "f" 5'

1316 3

SS matrix (which is approx.  
slightly plastic fines)  
permeable, stiff; glacial till.

13 JUL

8/17/79

MILLEROCK WATERSHED PROJECT  
FLOODWATER RETARDING DAM NO 1  
CHEMANGO COUNTY, NEW YORK  
LOGS OF TEST HOLES

U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

2

DATE	8/17/79	BY	W. J. [illegible]
TEST HOLE NO.	1316 3	TEST HOLE NO.	1316 3
TEST HOLE NO.	1316 3	TEST HOLE NO.	1316 3
TEST HOLE NO.	1316 3	TEST HOLE NO.	1316 3

WILL BROOK WATERSHED PROJECT  
SITE 105  
SUMMARY OF QUANTITIES  
FINAL PAYMENT

<u>Bid Item No. 1</u>	Mobilization Unit Price - \$32,100.00	Total Quantity - 1.000 Final Cost - \$32,100.00
<u>Bid Item No. 2</u>	Clearing, Class 3 Unit Price - \$1,500.00	Total Quantity - 1.5 Acre Final Cost - \$2,250.00
<u>Bid Item No. 3</u>	Clearing and Grubbing Unit Price - \$2,000.00	Total Quantity - 3.6 Acre Final Cost - \$7,200.00
<u>Bid Item No. 4</u>	Removal of Jester Unit Price - \$5,000.00	Total Quantity - 1.000 Final Cost - \$5,000.00
<u>Bid Item No. 5</u>	Excavation, Common, Type A Unit Price - \$21.00	Total Quantity - 10,153 C.Y. Final Cost - \$213,213.00
<u>Bid Item No. 14</u>	Excavation, Common, Type A Unit Price - \$11.00	Total Quantity - 1,487 C.Y. Final Cost - \$16,357.00
<u>Bid Item No. 13</u>	Excavation, Common, Type A Unit Price - \$21.00	Total Quantity - 371 C.Y. Final Cost - \$7,771.00
<u>Bid Item No. 5</u>	Excavation, Common, Type 3 Unit Price - \$21.00	Total Quantity - 1,500 C.Y. Final Cost - \$31,500.00
<u>Bid Item No. 14</u>	Excavation, Common, Type 3 Unit Price - \$21.00	Total Quantity - 145 C.Y. Final Cost - \$3,045.00
<u>Bid Item No. 7</u>	Excavation, Common, See above Spillway Unit Price - \$21.00	Total Quantity - 13,813 C.Y. Final Cost - \$290,073.00
<u>Bid Item No. 14</u>	Excavation, Common, See above Area A2 Unit Price - \$21.00	Total Quantity - 19,473 C.Y. Final Cost - \$408,933.00
<u>Bid Item No. 13</u>	Excavation, Common, Spillway, Rock Unit Price - \$10.00	Total Quantity - 17 C.Y. Final Cost - \$170.00
<u>Bid Item No. 14</u>	Excavation, Common, See above Pool Storage Unit Price - \$21.00	Total Quantity - 1000 C.Y. Final Cost - \$21,000.00
<u>Bid Item No. 8</u>	Access Road Unit Price - \$2,000.00	Total Quantity - 1.000 Final Cost - \$2,000.00
<u>Bid Item No. 9</u>	Earth Fill Unit Price - \$21.00	Total Quantity - 27,000 C.Y. Final Cost - \$567,000.00
<u>Bid Item No. 14</u>	Earth Fill Unit Price - \$21.00	Total Quantity - 420 C.Y. Final Cost - \$8,820.00
<u>Bid Item No. 10</u>	Earth Fill, Structure Spillway Unit Price - \$21.00	Total Quantity - 1000 C.Y. Final Cost - \$21,000.00
<u>Bid Item No. 11</u>	Earth Fill Unit Price - \$21.00	Total Quantity - 1000 C.Y. Final Cost - \$21,000.00
<u>Bid Item No. 12</u>	Gravel & Spread 1/4" - 1/2" Unit Price - \$1.00	Total Quantity - 2000 C.Y. Final Cost - \$2,000.00
<u>Bid Item No. 13</u>	Concrete, Reinforced, Class 4000 Unit Price - \$100.00	Total Quantity - 27.5 C.Y. Final Cost - \$2,750.00
<u>Bid Item No. 14</u>	Concrete, Reinforced, Non-Class 4000 Unit Price - \$100.00	Total Quantity - 9.7 C.Y. Final Cost - \$970.00
<u>Bid Item No. 15</u>	Concrete, Reinforced, Class 4000 Unit Price - \$70.00	Total Quantity - 15.5 C.Y. Final Cost - \$1,085.00
<u>Bid Item No. 16</u>	Concrete, Reinforced, Non-Class 4000 Unit Price - \$100.00	Total Quantity - 10.7 C.Y. Final Cost - \$1,070.00
<u>Bid Item No. 17</u>	Steel Reinforcement Unit Price - \$20.00	Total Quantity - 5,000 lbs. Final Cost - \$10,000.00

<u>Bid Item No. 15</u>	Reinforced Concrete Pressure Pipe, 18" Diameter Unit Price - \$100.00	Total Quantity - 100 L.F. Final Cost - \$10,000.00
<u>Bid Item No. 17</u>	Reinforced Concrete Pressure Pipe, 18" Diameter Unit Price - \$100.00	Total Quantity - 24 L.F. Final Cost - \$2,400.00
<u>Bid Item No. 18</u>	Asbestos-Cement Pipe, Conduits & Manholes - 6" Diameter Unit Price - \$5.00	Total Quantity - 435 L.F. Final Cost - \$2,175.00
<u>Bid Item No. 19</u>	Large Rock Storage, Equipment Placed Unit Price - \$10.00	Total Quantity - 135 C.Y. Final Cost - \$1,350.00
<u>Bid Item No. 10A</u>	Modified Large Rock Storage, Equipment Placed, River Area Unit Price - \$10.00	Total Quantity - 27 C.Y. Final Cost - \$270.00
<u>Bid Item No. 20</u>	Bedding Unit Price - \$14.00	Total Quantity - 97 C.Y. Final Cost - \$1,358.00
<u>Bid Item No. 20A</u>	Modified Bedding, River Area Unit Price - \$14.00	Total Quantity - 11 C.Y. Final Cost - \$154.00
<u>Bid Item No. 21</u>	Water Control Gate, 10' Dia. Unit Price - \$2,000.00	Total Quantity - 1.000 Final Cost - \$2,000.00
<u>Bid Item No. 22</u>	Miscellaneous Steel Work Unit Price - \$1,000.00	Total Quantity - 1.000 Final Cost - \$1,000.00
<u>Bid Item No. 23</u>	Flow Field Gates Unit Price - \$20.00	Total Quantity - 1000 L.F. Final Cost - \$20,000.00
<u>Bid Item No. 24</u>	Flow Field Gates Unit Price - \$20.00	Total Quantity - 200 L.F. Final Cost - \$4,000.00
<u>Bid Item No. 25</u>	Flow Field Gates Unit Price - \$20.00	Total Quantity - 10.5 Acre Final Cost - \$2,100.00
<u>Bid Item No. 26</u>	Flow Field Gates Unit Price - \$20.00	Total Quantity - 13.5 Acre Final Cost - \$2,700.00

TOTAL PROJECT COST = \$ 5,000,000.00

1

<u>Item No. 16</u>	Reinforced Concrete Pressure Pipe, 36" Diameter Unit Price = \$17.00	Total Quantity = 340 L.F. Final Cost = \$578.00
<u>Item No. 17</u>	Reinforced Concrete Pressure Pipe, 18" Diameter Unit Price = \$55.00	Total Quantity = 16 L.F. Final Cost = \$880.00
<u>Item No. 18</u>	Asbestos-Cement Pipe, Conduits & Drains - 5" Diameter Unit Price = \$5.00	Total Quantity = 425 L.F. Final Cost = \$2,125.00
<u>Item No. 19</u>	Loose Rock Riprap, Equipment Placed Unit Price = \$30.00	Total Quantity = 135 C.Y. Final Cost = \$4,050.00
<u>Item No. 20</u>	Modified Loose Rock Riprap, Equipment Placed, River Area Unit Price = \$40.00	Total Quantity = 27 C.Y. Final Cost = \$1,080.00
<u>Item No. 21</u>	Bedding Unit Price = \$14.00	Total Quantity = 97 C.Y. Final Cost = \$1,358.00
<u>Item No. 22</u>	Modified Bedding, River Area Unit Price = \$11.00	Total Quantity = 13 C.Y. Final Cost = \$143.00
<u>Item No. 23</u>	Water Control Gate, 27 Dia. Unit Price = \$4,500.00	Total Quantity = 1 GCS Final Cost = \$4,500.00
<u>Item No. 24</u>	Masselimestone Check Dam Unit Price = \$1,000.00	Total Quantity = 1 GCS Final Cost = \$1,000.00
<u>Item No. 25</u>	Open Field Fence Unit Price = \$10.00	Total Quantity = 1019 L.F. Final Cost = \$10,190.00
<u>Item No. 26</u>	Open Field Fence Unit Price = \$10.00	Total Quantity = 100 L.F. Final Cost = \$1,000.00
<u>Item No. 27</u>	Vegetative Treatment Unit Price = \$100.00	Total Quantity = 13.5 Acre Final Cost = \$1,350.00
<u>Item No. 28</u>	Native Site-Work Unit Price = \$1,500.00	Total Quantity = 13.5 Acre Final Cost = \$20,250.00

GRAND TOTAL = \$37,573.00

100 00000  
100 00000

U.S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE